

Schedule 1: Designer Information

Use one form for each individual who reviews and takes responsibility for design activities with respect to the project.

A. Project Information			
Building number, street name		Unit no.	Lot/con.
Municipality BRAMPTON	Postal code	Plan number/ other description	
B. Individual who reviews and takes responsibility for design activities			
Name MICHAEL O'ROURKE		Firm HVAC DESIGNS LTD.	
Street address 375 FINLEY AVE		Unit no. 202	Lot/con. N/A
Municipality AJAX	Postal code L1S 2E2	Province ONTARIO	E-mail info@hvacdesigns.ca
Telephone number (905) 619-2300	Fax number (905) 619-2375	Cell number ()	
C. Design activities undertaken by individual identified in Section B. [Building Code Table 3.5.2.1 OF Division C]			
☐ House ☐ Small Buildings ☐ Large Buildings ☐ Complex Buildings ☒ HVAC – House ☐ Building Services ☐ Detection, Lighting and Power ☐ Fire Protection ☐ Building Structural ☐ Plumbing – House ☐ Plumbing – All Buildings ☐ On-site Sewage Systems			
Description of designer's work HEAT LOSS / GAIN CALCULATIONS DUCT SIZING RESIDENTIAL MECHANICAL VENTILATION DESIGN SUMMARY RESIDENTIAL SYSTEM DESIGN per CSA-F280-12		Model: 6003 OPT IN-LAW Project: VALES OF HUMBER SOUTH	
D. Declaration of Designer			
I, <u>MICHAEL O'ROURKE</u> declare that (choose one as appropriate): (print name)			
☐ I review and take responsibility for the design work on behalf of a firm registered under subsection 3.2.4. of Division C, of the Building Code. I am qualified, and the firm is registered, in the appropriate classes/categories. Individual BCIN: _____ Firm BCIN: _____			
☒ I review and take responsibility for the design and am qualified in the appropriate category as an "other designer" under subsection 3.2.5. of Division C, of the Building Code. Individual BCIN: <u>19669</u> Basis for exemption from registration and qualification: <u>O.B.C SENTENCE 3.2.4.1 (4)</u>			
☐ The design work is exempt from the registration and qualification requirements of the Building Code. Basis for exemption from registration and qualification: _____			
I certify that:			
1. The information contained in this schedule is true to the best of my knowledge. 2. I have submitted this application with the knowledge and consent of the firm.			
April 7, 2022			
Date		Signature of Designer	

NOTE:

- For the purposes of this form, "individual" means the "person" referred to in Clause 3.2.4.7(1) d) of Division C, Article 3.2.5.1. of Division C, and all other persons who are exempt from qualification under Subsections 3.2.4. and 3.2.5. of Division C.
- Schedule 1 is not required to be completed by a holder of a license, temporary license, or a certificate of authorization, issued by the Ontario Association of Architects. Schedule 1 is also not required to be completed by a holder of a license to practise, a limited license to practise, or a certificate of authorization, issued by the Association of Professional Engineers of Ontario.

Application for a Permit Construct or Demolish – Effective January 1, 2015

SITE NAME: VALES OF HUMBER SOUTH										OPT IN-LAW					DATE Apr-22					WINTER NATURAL AIR CHANGE RATE 0.234					HEAT LOSS AT °F. 74		CSA-F280-12																
BUILDER: ROYAL PINE HOMES										TYPE: 6003					GFA: 5239					LO# 95294					SUMMER NATURAL AIR CHANGE RATE 0.076					HEAT GAIN AT °F. 11		SB-12 PERFORMANCE											
ROOM USE				GREAT				KIT				PANT				DIN				LIV				FOY				LIBR				PWD				LAUN				IN-LAW			
EXP. WALL				50				26				20				25				35				8				36				7				8				13			
CLG. HT.				11				11				11				11				11				21				11				11				12				11			
FACTORS																																											
GRS.WALL AREA		LOSS GAIN		550				286				220				275				385				168				396				77				96				143			
GLAZING				LOSS GAIN				LOSS GAIN				LOSS GAIN				LOSS GAIN				LOSS GAIN				LOSS GAIN				LOSS GAIN				LOSS GAIN				LOSS GAIN				LOSS GAIN			
NORTH		20.8	15.5	28	582	433	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	24	499	371			
EAST		20.8	41.0	0	0	0	0	0	0	0	0	0	0	0	0	48	997	1970	30	623	1231	70	1454	2873	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
SOUTH		20.8	24.4	14	291	342	0	0	0	0	0	0	0	0	37	769	903	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0		
WEST		20.8	41.0	48	997	1970	93	1932	3817	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
SKYLT.		34.1	100.3	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0		
DOORS		24.7	3.7	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	50	1233	183	0	0	0	0	0	0	0	0	0	0	0	0	20	493	73	0	0	0	0			
NET EXPOSED WALL		3.5	0.5	460	1595	236	193	669	99	220	763	113	238	825	122	337	1168	173	88	305	45	326	1130	168	77	267	40	76	264	39	119	413	61										
NET EXPOSED BSMT WALL ABOVE GR		3.5	0.5	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0			
EXPOSED CLG		1.3	0.6	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0			
NO ATTIC EXPOSED CLG		2.7	1.2	10	27	12	0	0	0	0	0	0	0	0	0	15	40	18	64	172	76	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0			
EXPOSED FLOOR		2.5	0.4	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0			
BASEMENT/CRAWL HEAT LOSS																																											
SLAB ON GRADE HEAT LOSS																																											
SUBTOTAL HT LOSS						3492						763						1594																									
SUB TOTAL HT GAIN																																											
LEVEL FACTOR / MULTIPLIER																																											
AIR CHANGE HEAT LOSS																																											
AIR CHANGE HEAT GAIN																																											
DUCT LOSS																																											
DUCT GAIN																																											
HEAT GAIN PEOPLE																																											
HEAT GAIN APPLIANCES/LIGHTS																																											
TOTAL HT LOSS BTU/H																																											
TOTAL HT GAIN x 1.3 BTU/H																																											

ROOM USE																							
EXP. WALL																							
CLG. HT.																							
GRS.WALL AREA	LOSS	GAIN																					
GLAZING																							
NORTH	20.8	15.5	14	291	217																		
EAST	20.8	41.0	0	0	0																		
SOUTH	20.8	24.4	0	0	0																		
WEST	20.8	41.0	0	0	0																		
SKYLT.	34.1	100.3	0	0	0																		
DOORS	24.7	3.7	0	0	0																		
NET EXPOSED WALL	3.5	0.5	184	638	95																		
NET EXPOSED BSMT WALL ABOVE GR	3.5	0.5	0	0	0																		
EXPOSED CLG	1.3	0.6	0	0	0																		
NO ATTIC EXPOSED CLG	2.7	1.2	0	0	0																		
EXPOSED FLOOR	2.5	0.4	0	0	0																		
BASEMENT/CRAWL HEAT LOSS																							
SLAB ON GRADE HEAT LOSS																							
SUBTOTAL HT LOSS																							
SUB TOTAL HT GAIN																							
LEVEL FACTOR / MULTIPLIER	0.30	0.40																					
AIR CHANGE HEAT LOSS																							
AIR CHANGE HEAT GAIN																							
DUCT LOSS																							
DUCT GAIN																							
HEAT GAIN PEOPLE	240																						
HEAT GAIN APPLIANCES/LIGHTS																							
TOTAL HT LOSS BTU/H																							
TOTAL HT GAIN x 1.3 BTU/H																							

TOTAL HEAT GAIN BTU/H: 71549 TONS: 5.96 LOSS DUE TO VENTILATION LOAD BTU/H: 6010 STRUCTURAL HEAT LOSS: 73887 TOTAL COMBINED HEAT LOSS BTU/H: 79897

SITE NAME: VALES OF HUMBER SOUTH				OPT IN-LAW				DATE Apr-22				WINTER NATURAL AIR CHANGE RATE 0.234				HEAT LOSS AT °F. 74				CSA-F280-12			
BUILDER: ROYAL PINE HOMES				TYPE: 6003				GFA: 5239				SUMMER NATURAL AIR CHANGE RATE 0.076				HEAT GAIN ΔT °F. 11				SB-12 PERFORMANCE			
ROOM USE		PRI		ENS		DRESS		BED-2		BED-3		BED-4		BED-5		ENS-2		ENS-3		ENS-4			
EXP. WALL		37		11		14		43		39		41		33		10		10		7			
CLG. HT.		10		9		9		9		10		10		10		9		9		9			
FACTORS																							
GRS.WALL AREA		370		99		126		387		390		410		330		90		90		63			
GLAZING		LOSS GAIN		LOSS GAIN		LOSS GAIN		LOSS GAIN		LOSS GAIN		LOSS GAIN		LOSS GAIN		LOSS GAIN		LOSS GAIN		LOSS GAIN			
NORTH		20.8	15.5	0	0	0	0	0	0	0	0	0	0	0	0	8	166	124	8	166	124	0	0
EAST		20.8	41.0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	8	166
SOUTH		20.8	24.4	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
WEST		20.8	41.0	36	748	1478	18	374	739	0	0	0	0	0	0	0	0	0	0	0	0	0	0
SKYLT.		34.1	100.3	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
DOORS		24.7	3.7	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
NET EXPOSED WALL		3.5	0.5	334	1158	172	81	281	42	108	374	56	351	1217	180	335	1162	172	284	985	146	82	284
NET EXPOSED BSMT WALL ABOVE GR		3.5	0.5	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
EXPOSED CLG		1.3	0.6	570	714	318	209	262	116	196	246	109	380	476	212	313	392	174	348	436	194	163	204
NO ATTIC EXPOSED CLG		2.7	1.2	0	0	0	0	0	0	0	0	0	50	134	60	30	81	36	70	188	84	0	0
EXPOSED FLOOR		2.5	0.4	0	0	0	0	0	0	0	0	0	275	685	102	0	0	0	0	0	0	0	0
BASEMENT/CRAWL HEAT LOSS				0		0		0		0		0		0		0		0		0		0	
SLAB ON GRADE HEAT LOSS				0		0		0		0		0		0		0		0		0		0	
SUBTOTAL HT LOSS				2620			917			994			2441			3238			2332			626	
SUB TOTAL HT GAIN					1967			897		604			1870			2117			3481			2209	
LEVEL FACTOR / MULTIPLIER		0.20	0.27				0.20	0.27		0.20	0.27		0.20	0.27		0.20	0.27		0.20	0.27		0.20	0.27
AIR CHANGE HEAT LOSS				702			245			266			654			867			625			168	
AIR CHANGE HEAT GAIN					102			47		31			97			110			181			13	
DUCT LOSS				0			0			0			411			0			0			0	
DUCT GAIN					0		0			0			378			0			0			0	
HEAT GAIN PEOPLE		240		2		480	0		0	1		240	1		240	1		240	0		0		0
HEAT GAIN APPLIANCES/LIGHTS					1314		1314			0		1314			1314			1314			1314		0
TOTAL HT LOSS BTU/H				3322			1162			1260			3095			4516			4103			2957	
TOTAL HT GAIN x 1.3 BTU/H				5022			2935			826			4577			5406			6780			5040	

ROOM USE		ENS-5																					
EXP. WALL		9																					
CLG. HT.		9																					
FACTORS																							
GRS.WALL AREA		81																					
GLAZING		LOSS GAIN		LOSS GAIN																			
NORTH		20.8	15.5	0	0	0																	
EAST		20.8	41.0	0	0	0																	
SOUTH		20.8	24.4	9	187	220																	
WEST		20.8	41.0	0	0	0																	
SKYLT.		34.1	100.3	0	0	0																	
DOORS		24.7	3.7	0	0	0																	
NET EXPOSED WALL		3.5	0.5	72	250	37																	
NET EXPOSED BSMT WALL ABOVE GR		3.5	0.5	0	0	0																	
EXPOSED CLG		1.3	0.6	117	147	65																	
NO ATTIC EXPOSED CLG		2.7	1.2	0	0	0																	
EXPOSED FLOOR		2.5	0.4	0	0	0																	
BASEMENT/CRAWL HEAT LOSS				0																			
SLAB ON GRADE HEAT LOSS				0																			
SUBTOTAL HT LOSS				583																			
SUB TOTAL HT GAIN					322																		
LEVEL FACTOR / MULTIPLIER		0.20	0.27																				
AIR CHANGE HEAT LOSS				156																			
AIR CHANGE HEAT GAIN					17																		
DUCT LOSS				0																			
DUCT GAIN					0																		
HEAT GAIN PEOPLE		240		0		0																	
HEAT GAIN APPLIANCES/LIGHTS					0																		
TOTAL HT LOSS BTU/H				739																			
TOTAL HT GAIN x 1.3 BTU/H				440																			

TOTAL HEAT GAIN BTU/H: 71549 TONS: 5.96 LOSS DUE TO VENTILATION LOAD BTU/H: 6010 STRUCTURAL HEAT LOSS: 73887 TOTAL COMBINED HEAT LOSS BTU/H: 79897

SITE NAME: VALES OF HUMBER SOUTH
BUILDER: ROYAL PINE HOMES

OPT IN-LAW
TYPE: 6003

DATE: Apr-22

GFA: 5239 LO# 95294

FURNACE 1

HEATING CFM 1145 COOLING CFM 1145
TOTAL HEAT LOSS 50,246 TOTAL HEAT GAIN 35,351
AIR FLOW RATE CFM 22.79 AIR FLOW RATE CFM 32.39

furnace pressure 0.6
furnace filter 0.05
a/c coil pressure 0.2
available pressure
for s/a & r/a 0.35

FURNACE HEAT LOSS +
HRV / ERV HEAT LOSS
= 53251 BTUH

#*CARRIER

59SP5A-60-14

FAN SPEED 60

LOW 0

MEDLOW 785

MEDIUM 960

MEDIUM HIGH 1145

HIGH 1440

AFUE = 97 %
INPUT (BTU/H) = 60,000
OUTPUT (BTU/H) = 58,000

DESIGN CFM = 1145
CFM @ .6" E.S.P.

TEMPERATURE RISE 47 °F

RUN COUNT	4th	3rd	2nd	1st	Bas
S/A	0	0	0	20	8
R/A	0	0	0	5	1

All S/A diffusers 4"x10" unless noted otherwise on layout.

All S/A runs 5"Ø unless noted otherwise on layout.

RUN #	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24
ROOM NAME	GREAT	GREAT	GREAT	KIT	KIT	KIT	PANT	DIN	DIN	LIV	LIV	FOY	LIBR	LIBR	LIBR	PWD	LAUN	IN-LAW	IN-LAW	I-ENS	BAS	BAS	BAS	BAS
RM LOSS MBH.	1.63	1.63	1.63	1.21	1.21	1.21	1.07	1.11	1.11	1.54	1.54	3.26	1.20	1.20	1.20	0.37	1.06	0.64	0.64	1.30	3.06	3.06	3.06	3.06
CFM PER RUN HEAT	37	37	37	28	28	28	24	25	25	35	35	74	27	27	27	9	24	15	15	30	70	70	70	70
RM GAIN MBH.	1.93	1.93	1.93	2.35	2.35	2.35	0.15	1.55	1.55	2.33	2.33	2.10	1.96	1.96	1.96	0.05	1.86	1.31	1.31	0.43	0.20	0.20	0.20	0.20
CFM PER RUN COOLING	63	63	63	76	76	76	5	50	50	76	76	68	63	63	63	2	60	42	42	14	7	7	7	7
ADJUSTED PRESSURE	0.17	0.17	0.17	0.17	0.17	0.17	0.17	0.17	0.17	0.17	0.17	0.17	0.17	0.17	0.17	0.17	0.17	0.17	0.17	0.17	0.17	0.17	0.17	0.17
ACTUAL DUCT LGH.	55	69	52	43	37	38	36	16	16	34	29	27	39	47	48	32	46	53	58	64	43	33	64	54
EQUIVALENT LENGTH	150	120	120	120	120	130	150	100	100	110	110	110	130	170	170	90	220	190	190	200	140	150	130	140
TOTAL EFFECTIVE LENGTH	205	189	172	163	157	168	186	116	116	144	139	137	169	217	218	122	266	243	248	264	183	183	194	194
ADJUSTED PRESSURE	0.08	0.09	0.1	0.11	0.11	0.1	0.09	0.15	0.15	0.12	0.12	0.13	0.1	0.08	0.08	0.14	0.06	0.07	0.07	0.07	0.09	0.09	0.09	0.09
ROUND DUCT SIZE	5	5	5	5	5	5	4	5	5	5	5	5	5	5	5	4	5	5	5	4	5	5	5	5
HEATING VELOCITY (ft/min)	272	272	272	206	206	206	275	184	184	257	257	543	198	198	198	103	176	110	110	344	514	514	514	514
COOLING VELOCITY (ft/min)	463	463	463	558	558	558	57	367	367	558	558	499	463	463	463	23	441	308	308	161	51	51	51	51
OUTLET GRILL SIZE	3X10	3X10	3X10	3X10	3X10	3X10	3X10	3X10	3X10	3X10	3X10	3X10	3X10	3X10	3X10	3X10	3X10	3X10	3X10	3X10	3X10	3X10	3X10	3X10
TRUNK	A	A	A	B	B	B	B	C	E	D	D	D	D	D	D	E	A	A	A	A	B	B	A	A

RUN #	25	26	27	28
ROOM NAME	BAS	BAS	BAS	BAS
RM LOSS MBH.	3.06	3.06	3.06	3.06
CFM PER RUN HEAT	70	70	70	70
RM GAIN MBH.	0.20	0.20	0.20	0.20
CFM PER RUN COOLING	7	7	7	7
ADJUSTED PRESSURE	0.17	0.17	0.17	0.17
ACTUAL DUCT LGH.	17	19	28	40
EQUIVALENT LENGTH	100	120	160	150
TOTAL EFFECTIVE LENGTH	117	139	188	190
ADJUSTED PRESSURE	0.15	0.12	0.09	0.09
ROUND DUCT SIZE	5	5	5	5
HEATING VELOCITY (ft/min)	514	514	514	514
COOLING VELOCITY (ft/min)	51	51	51	51
OUTLET GRILL SIZE	3X10	3X10	3X10	3X10
TRUNK	E	E	D	D

SUPPLY AIR TRUNK SIZE													RETURN AIR TRUNK SIZE												
TRUNK	STATIC	ROUND	RECT	VELOCITY				TRUNK	STATIC	ROUND	RECT	VELOCITY				TRUNK	STATIC	ROUND	RECT	VELOCITY					
CFM	PRESS.	DUCT	DUCT			(ft/min)		CFM	PRESS.	DUCT	DUCT			(ft/min)	CFM	PRESS.	DUCT	DUCT			(ft/min)				
TRUNK A	335	0.06	10	12	x	8	503	TRUNK G	0	0.00	0	0	x	8	0	TRUNK O	0	0.06	0	0	x	8	0		
TRUNK B	248	0.09	8.1	8	x	8	558	TRUNK H	0	0.00	0	0	x	8	0	TRUNK P	0	0.06	0	0	x	8	0		
TRUNK C	608	0.06	12.5	18	x	8	608	TRUNK I	0	0.00	0	0	x	8	0	TRUNK Q	0	0.06	0	0	x	8	0		
TRUNK D	365	0.08	9.6	12	x	8	548	TRUNK J	0	0.00	0	0	x	8	0	TRUNK R	0	0.06	0	0	x	8	0		
TRUNK E	539	0.08	11.1	16	x	8	606	TRUNK K	0	0.00	0	0	x	8	0	TRUNK S	0	0.06	0	0	x	8	0		
TRUNK F	0	0.00	0	0	x	8	0	TRUNK L	0	0.00	0	0	x	8	0	TRUNK T	0	0.06	0	0	x	8	0		

RETURN AIR #	1	2	3	4	5											BR								
AIR VOLUME	230	230	165	155	135	0	0	0	0	0	0	0	0	0	0	230	TRUNK W	0	0.06	0	0	x	8	0
PLENUM PRESSURE	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	TRUNK X	825	0.06	14	22	x	8	675
ACTUAL DUCT LGH.	60	27	32	48	68	1	1	1	1	1	1	1	1	1	1	21	TRUNK Y	320	0.06	9.8	12	x	8	480
EQUIVALENT LENGTH	200	145	155	160	160	0	0	0	0	0	0	0	0	0	0	150	TRUNK Z	365	0.06	10.3	12	x	8	548
TOTAL EFFECTIVE LH	260	172	187	208	228	1	1	1	1	1	1	1	1	1	1	171	DROP	1145	0.06	15.9	24	x	10	687
ADJUSTED PRESSURE	0.06	0.09	0.08	0.07	0.06	14.80	14.80	14.80	14.80	14.80	14.80	14.80	14.80	14.80	14.80	0.09								
ROUND DUCT SIZE	8.7	7.9	7.1	7.2	7.1	0	0	0	0	0	0	0	0	0	0	7.9								
INLET GRILL SIZE	8	8	8	8	8	0	0	0	0	0	0	0	0	0	0	8								
	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X								
INLET GRILL SIZE	30	24	14	14	14	0	0	0	0	0	0	0	0	0	0	24								

SITE NAME: VALES OF HUMBER SOUTH
BUILDER: ROYAL PINE HOMES

OPT IN-LAW
TYPE: 6003

DATE: Apr-22

GFA: 5239 LO# 95294

FURNACE 2

HEATING CFM 1040 COOLING CFM 1040
TOTAL HEAT LOSS 23,641 TOTAL HEAT GAIN 35,753
AIR FLOW RATE CFM 43.99 AIR FLOW RATE CFM 29.09

furnace pressure 0.6
furnace filter 0.05
a/c coil pressure 0.2
available pressure for s/a & r/a 0.35

**FURNACE HEAT LOSS +
HRV / ERV HEAT LOSS
= 26646 BTUH**
#*CARRIER
59SP5A-40-12
40

AFUE = 97 %

INPUT (BTU/H) = 40,000

OUTPUT (BTU/H) = **39,000**

FAN SPEED

LOW 0

MEDLOW 0

MEDIUM 0

MEDIUM HIGH 770

HIGH 1040

DESIGN CFM = **1040**

CFM @ .6" E.S.P.

TEMPERATURE RISE 35 °F

RUN COUNT	4th	3rd	2nd	1st	Bas
S/A	0	0	21	0	0
R/A	0	0	6	0	0

All S/A diffusers 4"x10" unless noted otherwise on layout.

All S/A runs 5"Ø unless noted otherwise on layout.

RUN #	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21
ROOM NAME	PRI	PRI	PRI	ENS	ENS	DRESS	BED-2	BED-2	BED-2	ENS-2	BED-3	BED-3	BED-3	ENS-3	BED-4	BED-4	BED-4	ENS-4	BED-5	BED-5	ENS-5
RM LOSS MBH.	1.11	1.11	1.11	0.58	0.58	1.26	1.03	1.03	1.03	0.79	1.51	1.51	1.51	0.79	1.37	1.37	1.37	0.90	1.48	1.48	0.74
CFM PER RUN HEAT	49	49	49	26	26	55	45	45	45	35	66	66	66	35	60	60	60	40	65	65	33
RM GAIN MBH.	1.67	1.67	1.67	1.47	1.47	0.83	1.53	1.53	1.53	2.04	1.80	1.80	1.80	2.04	2.26	2.26	2.26	0.64	2.52	2.52	0.44
CFM PER RUN COOLING	49	49	49	43	43	24	44	44	44	59	52	52	52	59	66	66	66	19	73	73	13
ADJUSTED PRESSURE	0.17	0.17	0.17	0.17	0.17	0.17	0.17	0.17	0.17	0.17	0.17	0.17	0.17	0.17	0.17	0.17	0.17	0.17	0.17	0.17	0.17
ACTUAL DUCT LGH.	63	70	76	65	47	39	74	80	86	66	64	68	69	68	54	61	64	54	43	45	41
EQUIVALENT LENGTH	200	200	200	180	160	160	180	180	190	150	130	140	150	150	160	150	160	120	130	150	130
TOTAL EFFECTIVE LENGTH	263	270	276	245	207	199	254	260	276	216	194	208	219	218	214	211	224	174	173	195	171
ADJUSTED PRESSURE	0.07	0.06	0.06	0.07	0.08	0.09	0.07	0.07	0.06	0.08	0.09	0.08	0.08	0.08	0.08	0.08	0.08	0.1	0.1	0.09	0.1
ROUND DUCT SIZE	5	5	5	5	4	5	5	5	5	5	5	5	5	5	5	5	5	4	5	5	4
HEATING VELOCITY (ft/min)	360	360	360	191	298	404	330	330	330	257	485	485	485	257	441	441	441	459	477	477	379
COOLING VELOCITY (ft/min)	360	360	360	316	493	176	323	323	323	433	382	382	382	433	485	485	485	218	536	536	149
OUTLET GRILL SIZE	3X10	3X10	3X10	3X10	3X10	3X10	3X10	3X10	3X10	3X10	3X10	3X10	3X10	3X10	3X10	3X10	3X10	3X10	3X10	3X10	3X10
TRUNK	C	C	C	D	D	D	C	C	C	D	B	B	B	D	A	A	A	B	A	A	B

RUN #	ROOM NAME	RM LOSS MBH.	CFM PER RUN HEAT	RM GAIN MBH.	CFM PER RUN COOLING	ADJUSTED PRESSURE	ACTUAL DUCT LGH.	EQUIVALENT LENGTH	TOTAL EFFECTIVE LENGTH	ADJUSTED PRESSURE	ROUND DUCT SIZE	HEATING VELOCITY (ft/min)	COOLING VELOCITY (ft/min)	OUTLET GRILL SIZE	TRUNK
1	PRI	1.11	49	1.67	49	0.17	63	200	263	0.07	5	360	360	3X10	C
2	PRI	1.11	49	1.67	49	0.17	70	200	270	0.06	5	360	360	3X10	C
3	PRI	1.11	49	1.67	49	0.17	76	200	276	0.06	5	360	360	3X10	C
4	ENS	0.58	26	1.47	43	0.17	65	180	245	0.07	5	191	316	3X10	D
5	ENS	0.58	26	1.47	43	0.17	47	160	207	0.08	4	298	493	3X10	D
6	DRESS	1.26	55	0.83	24	0.17	39	160	199	0.09	5	404	176	3X10	D
7	BED-2	1.03	45	1.53	44	0.17	74	180	254	0.07	5	330	323	3X10	C
8	BED-2	1.03	45	1.53	44	0.17	80	180	260	0.07	5	330	323	3X10	C
9	BED-2	1.03	45	1.53	44	0.17	86	190	276	0.06	5	330	323	3X10	C
10	ENS-2	0.79	35	2.04	59	0.17	66	150	216	0.08	5	257	433	3X10	D
11	BED-3	1.51	66	1.80	52	0.17	64	130	194	0.09	5	485	382	3X10	B
12	BED-3	1.51	66	1.80	52	0.17	68	140	208	0.08	5	485	382	3X10	B
13	BED-3	1.51	66	1.80	52	0.17	69	150	219	0.08	5	485	382	3X10	B
14	ENS-3	0.79	35	2.04	59	0.17	68	150	218	0.08	5	257	433	3X10	D
15	BED-4	1.37	60	2.26	66	0.17	54	160	214	0.08	5	441	485	3X10	A
16	BED-4	1.37	60	2.26	66	0.17	61	150	211	0.08	5	441	485	3X10	A
17	BED-4	1.37	60	2.26	66	0.17	64	160	224	0.08	5	441	485	3X10	A
18	ENS-4	0.90	40	0.64	19	0.17	54	120	174	0.1	4	459	218	3X10	B
19	BED-5	1.48	65	2.52	73	0.17	43	130	173	0.1	5	477	536	3X10	A
20	BED-5	1.48	65	2.52	73	0.17	45	150	195	0.09	5	477	536	3X10	A
21	ENS-5	0.74	33	0.44	13	0.17	41	130	171	0.1	4	379	149	3X10	B

SUPPLY AIR TRUNK SIZE															RETURN AIR TRUNK SIZE														
	TRUNK	STATIC	ROUND	RECT		VELOCITY		TRUNK	STATIC	ROUND	RECT		VELOCITY		TRUNK	STATIC	ROUND	RECT		VELOCITY									
	CFM	PRESS.	DUCT	DUCT		(ft/min)		CFM	PRESS.	DUCT	DUCT		(ft/min)		CFM	PRESS.	DUCT	DUCT		(ft/min)									
TRUNK A	310	0.08	9	12	x	8	465	TRUNK G	0	0.00	0	0	x	8	0	TRUNK O	0	0.06	0	0	x	8	0						
TRUNK B	581	0.08	11.4	18	x	8	581	TRUNK H	0	0.00	0	0	x	8	0	TRUNK P	0	0.06	0	0	x	8	0						
TRUNK C	282	0.06	9.4	10	x	8	508	TRUNK I	0	0.00	0	0	x	8	0	TRUNK Q	0	0.06	0	0	x	8	0						
TRUNK D	459	0.06	11.3	14	x	8	590	TRUNK J	0	0.00	0	0	x	8	0	TRUNK R	0	0.06	0	0	x	8	0						
TRUNK E	0	0.00	0	0	x	8	0	TRUNK K	0	0.00	0	0	x	8	0	TRUNK S	0	0.06	0	0	x	8	0						
TRUNK F	0	0.00	0	0	x	8	0	TRUNK L	0	0.00	0	0	x	8	0	TRUNK T	0	0.06	0	0	x	8	0						
									</																				

RETURN AIR #	1	2	3	4	5	6																BR
AIR VOLUME	260	130	260	130	130	130	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
PLENUM PRESSURE	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	
ACTUAL DUCT LGH.	50	77	92	72	44	51	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	
EQUIVALENT LENGTH	165	180	175	180	175	205	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
TOTAL EFFECTIVE LH	215	257	267	252	219	256	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	
ADJUSTED PRESSURE	0.07	0.06	0.06	0.06	0.07	0.06	14.80	14.80	14.80	14.80	14.80	14.80	14.80	14.80	14.80	14.80	14.80	14.80	14.80	14.80	14.80	
ROUND DUCT SIZE	8.8	7	9.1	7	6.8	7	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
INLET GRILL SIZE	8	8	8	8	8	8	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	
INLET GRILL SIZE	30	14	30	14	14	14	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	

TYPE: 6003
SITE NAME: VALES OF HUMBER SOUTH

LO # 95294
OPT IN-LAW

RESIDENTIAL MECHANICAL VENTILATION DESIGN SUMMARY

COMBUSTION APPLIANCES		9.32.3.1(1)
a)	☒ Direct vent (sealed combustion) only	
b)	☐ Positive venting induced draft (except fireplaces)	
c)	☐ Natural draft, B-vent or induced draft gas fireplace	
d)	☐ Solid Fuel (including fireplaces)	
e)	☐ No Combustion Appliances	

HEATING SYSTEM	
☒ Forced Air	☐ Non Forced Air
☐ Electric Space Heat	

HOUSE TYPE		9.32.1(2)
☒ I	Type a) or b) appliance only, no solid fuel	
☐ II	Type I except with solid fuel (including fireplaces)	
☐ III	Any Type c) appliance	
☐ IV	Type I, or II with electric space heat	
☐	Other: Type I, II or IV no forced air	

SYSTEM DESIGN OPTIONS		O.N.H.W.P.
☐ 1	Exhaust only/Forced Air System	
☐ 2	HRV with Ducting/Forced Air System	
☒ 3	HRV Simplified/connected to forced air system	
☐ 4	HRV with Ducting/non forced air system	
☐	Part 6 Design	

TOTAL VENTILATION CAPACITY		9.32.3.3(1)
Basement + Master Bedroom	<u>2</u> @ 21.2 cfm	<u>42.4</u> cfm
Other Bedrooms	<u>5</u> @ 10.6 cfm	<u>53</u> cfm
Kitchen & Bathrooms	<u>8</u> @ 10.6 cfm	<u>84.8</u> cfm
Other Rooms	<u>6</u> @ 10.6 cfm	<u>63.6</u> cfm
Table 9.32.3.A.	TOTAL	<u>243.8</u> cfm

PRINCIPAL VENTILATION CAPACITY REQUIRED		9.32.3.4.(1)
6 Bedrooms		
As Per Ashrea 62.2 Dwelling- Unit Ventilation		
4.1.1 Total Ventilation Rate		
$Q_{tot}=0.03A_{floor}+7.5(N_{br}+1)$		
TOTAL		<u>209.7</u> cfm

SUPPLEMENTAL VENTILATION CAPACITY		9.32.3.5.
Total Ventilation Capacity	<u>243.8</u>	cfm
Less Principal Ventil. Capacity	<u>150</u>	cfm
Required Supplemental Capacity	<u>93.8</u>	cfm

PRINCIPAL EXHAUST FAN CAPACITY	
Model:	VANEE V150H
Location:	BSMT
<u>150.0</u> cfm	☒ HVI Approved

PRINCIPAL EXHAUST HEAT LOSS CALCULATION				
CFM	ΔT °F	FACTOR	% LOSS	
150.0 CFM	X 74 F	X 1.08	X	0.25

SUPPLEMENTAL FANS		BY INSTALLING CONTRACTOR		
Location	Model	cfm	HVI	Sones
ENS	BY INSTALLING CONTRACTOR	50	☒	3.5
ENS-2	BY INSTALLING CONTRACTOR	50	☒	3.5
ENS-3	BY INSTALLING CONTRACTOR	50	☒	3.5
ENS-4	BY INSTALLING CONTRACTOR	50	☒	3.5

HEAT RECOVERY VENTILATOR		9.32.3.11.
Model:	VANEE V150H	INSTALL 2 HRV / ERV's
<u>150</u>	cfm high	<u>35</u> cfm low
<u>75</u>	% Sensible Efficiency @ 32 deg F (0 deg C)	☒ HVI Approved

LOCATION OF INSTALLATION	
Lot:	Concession
Township	Plan:
Address	
Roll #	Building Permit #

BUILDER:	
ROYAL PINE HOMES	
Name:	
Address:	
City:	
Telephone #:	Fax #:

INSTALLING CONTRACTOR	
Name:	
Address:	
City:	
Telephone #:	Fax #:

DESIGNER CERTIFICATION	
I hereby certify that this ventilation system has been designed in accordance with the Ontario Building Code.	
Name:	HVAC Designs Ltd.
Signature:	<i>Michael O'Rourke</i>
HRAI #	001820
Date:	April-22

CSA F280-12 Residential Heat Loss and Heat Gain Calculations																																																													
Formula Sheet (For Air Leakage / Ventilation Calculation)																																																													
LO#: 95294		Model: 6003		Builder: ROYAL PINE HOMES																																																									
				Date: 2022-04-07																																																									
Volume Calculation			Air Change & Delta T Data																																																										
House Volume <table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th>Level</th> <th>Floor Area (ft²)</th> <th>Floor Height (ft)</th> <th>Volume (ft³)</th> </tr> </thead> <tbody> <tr> <td>Bsmt</td> <td>2540</td> <td>10</td> <td>25400</td> </tr> <tr> <td>First</td> <td>2540</td> <td>11</td> <td>27940</td> </tr> <tr> <td>Second</td> <td>2803</td> <td>9</td> <td>25227</td> </tr> <tr> <td>Third</td> <td>0</td> <td>9</td> <td>0</td> </tr> <tr> <td>Fourth</td> <td>0</td> <td>9</td> <td>0</td> </tr> <tr> <td colspan="2" style="text-align: right;">Total:</td> <td></td> <td>78,567.0 ft³</td> </tr> <tr> <td colspan="2" style="text-align: right;">Total:</td> <td></td> <td>2224.8 m³</td> </tr> </tbody> </table>			Level	Floor Area (ft²)	Floor Height (ft)	Volume (ft³)	Bsmt	2540	10	25400	First	2540	11	27940	Second	2803	9	25227	Third	0	9	0	Fourth	0	9	0	Total:			78,567.0 ft³	Total:			2224.8 m³	<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 80%;">WINTER NATURAL AIR CHANGE RATE</td> <td style="width: 20%;">0.234</td> </tr> <tr> <td>SUMMER NATURAL AIR CHANGE RATE</td> <td>0.076</td> </tr> </table> <table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th colspan="5" style="text-align: center;">Design Temperature Difference</th> </tr> <tr> <th></th> <th>Tin °C</th> <th>Tout °C</th> <th>ΔT °C</th> <th>ΔT °F</th> </tr> <tr> <td>Winter DTDh</td> <td>22</td> <td>-19</td> <td>41</td> <td>74</td> </tr> <tr> <td>Summer DTDc</td> <td>24</td> <td>30</td> <td>6</td> <td>11</td> </tr> </table>			WINTER NATURAL AIR CHANGE RATE	0.234	SUMMER NATURAL AIR CHANGE RATE	0.076	Design Temperature Difference						Tin °C	Tout °C	ΔT °C	ΔT °F	Winter DTDh	22	-19	41	74	Summer DTDc	24	30	6	11
Level	Floor Area (ft²)	Floor Height (ft)	Volume (ft³)																																																										
Bsmt	2540	10	25400																																																										
First	2540	11	27940																																																										
Second	2803	9	25227																																																										
Third	0	9	0																																																										
Fourth	0	9	0																																																										
Total:			78,567.0 ft³																																																										
Total:			2224.8 m³																																																										
WINTER NATURAL AIR CHANGE RATE	0.234																																																												
SUMMER NATURAL AIR CHANGE RATE	0.076																																																												
Design Temperature Difference																																																													
	Tin °C	Tout °C	ΔT °C	ΔT °F																																																									
Winter DTDh	22	-19	41	74																																																									
Summer DTDc	24	30	6	11																																																									
5.2.3.1 Heat Loss due to Air Leakage			6.2.6 Sensible Gain due to Air Leakage																																																										
$HL_{airb} = LR_{airh} \times \frac{V_b}{3.6} \times DTD_h \times 1.2$ 0.234 x 617.99 x 41 °C x 1.2 = 7165 W = 24448 Btu/h			$HG_{salb} = LR_{airc} \times \frac{V_b}{3.6} \times DTD_c \times 1.2$ = 0.076 x 617.99 x 6 °C x 1.2 = 345 W = 1178 Btu/h																																																										
5.2.3.2 Heat Loss due to Mechanical Ventilation			6.2.7 Sensible heat Gain due to Ventilation																																																										
$HL_{vairb} = PVC \times DTD_h \times 1.08 \times (1 - E) \times 2 \text{ HRV / ERV's}$ 300 CFM x 74 °F x 1.08 x 0.25 = 6010 Btu/h			$HL_{vairb} = PVC \times DTD_h \times 1.08 \times (1 - E)$ 300 CFM x 11 °F x 1.08 x 0.25 = 891 Btu/h																																																										
5.2.3.3 Calculation of Air Change Heat Loss for Each Room (Floor Multiplier Section)																																																													
$HL_{airr} = \text{Level Factor} \times HL_{airbv} \times \{(HL_{agcr} + HL_{bgcr}) \div (HL_{agclevel} + HL_{bgclevel})\}$																																																													
Level	Level Factor (LF)	HLairve Air Leakage + Ventilation Heat Loss (Btu/h)	Level Conductive Heat Loss: (HL _{clevel})	Air Leakage Heat Loss Multiplier (LF x HLairbv / HLlevel)																																																									
1	0.5	24,448	12,251	0.998																																																									
2	0.3		18,437	0.398																																																									
3	0.2		18,259	0.268																																																									
4	0		0	0.000																																																									
5	0		0	0.000																																																									
*HLairbv = Air leakage heat loss + ventilation heat loss *For a balanced or supply only ventilation system HLairve = 0																																																													
				Michael O'Rourke BCIN# 19669 																																																									

HEAT LOSS AND GAIN SUMMARY SHEET

MODEL: 6003	OPT IN-LAW	BUILDER: ROYAL PINE HOMES
SFQT: 5239	LO# 95294	SITE: VALES OF HUMBER SOUTH

DESIGN ASSUMPTIONS

HEATING	°F	COOLING	°F
OUTDOOR DESIGN TEMP.	-2	OUTDOOR DESIGN TEMP.	86
INDOOR DESIGN TEMP.	72	INDOOR DESIGN TEMP. (MAX 75°F)	75
		WINDOW SHGC	0.60

BUILDING DATA

ATTACHMENT:	DETACHED	# OF STORIES (+BASEMENT):	3
FRONT FACES:	EAST	ASSUMED (Y/N):	Y
AIR CHANGES PER HOUR:	2.50	ASSUMED (Y/N):	Y
AIR TIGHTNESS CATEGORY:	TIGHT	ASSUMED (Y/N):	Y
WIND EXPOSURE:	SHELTERED	ASSUMED (Y/N):	Y
HOUSE VOLUME (ft ³):	78567.0	ASSUMED (Y/N):	Y
INTERNAL SHADING:	BLINDS/CURTAINS	ASSUMED OCCUPANTS:	7
INTERIOR LIGHTING LOAD (Btu/h/ft ²):	2.50	DC BRUSHLESS MOTOR (Y/N):	Y
FOUNDATION CONFIGURATION	BCIN_1	DEPTH BELOW GRADE:	7.0 ft
LENGTH: 68.0 ft	WIDTH: 52.0 ft	EXPOSED PERIMETER:	240.0 ft

2012 OBC - COMPLIANCE PACKAGE**Component****Compliance Package
SB-12 PERFORMANCE****Nominal Min. Eff.**

Ceiling with Attic Space Minimum RSI (R)-Value	60	59.22
Ceiling Without Attic Space Minimum RSI (R)-Value	31	27.65
Exposed Floor Minimum RSI (R)-Value	31	29.80
Walls Above Grade Minimum RSI (R)-Value	22+1.5	21.40
Basement Walls Minimum RSI (R)-Value	20	21.12
Below Grade Slab Entire surface > 600 mm below grade Minimum RSI (R)-Value	-	-
Edge of Below Grade Slab ≤ 600 mm Below Grade Minimum RSI (R)-Value	10	10
Heated Slab or Slab ≤ 600 mm below grade Minimum RSI (R)-Value	10	11.13
Windows and Sliding Glass Doors Maximum U-Value	1.6	-
Skylights Maximum U-Value	2.6	-
Space Heating Equipment Minimum AFUE	0.96	-
HRV Minimum Efficiency	75%	-
Domestic Hot Water Heater Minimum EF	0.9	-


INDIVIDUAL BCIN: 19669

MICHAEL O'ROURKE



Residential Foundation Thermal Load Calculator

Supplemental tool for CAN/CSA-F280

Weather Station Description		
Province:	Ontario	
Region:	Brampton	
Site Description		
Soil Conductivity:	Normal conductivity: dry sand, loam, clay	
Water Table:	Normal (7-10 m, 23-33 ft)	
Foundation Dimensions		
Floor Length (m):	20.7	
Floor Width (m):	15.8	
Exposed Perimeter (m):	0.0	
Wall Height (m):	3.0	
Depth Below Grade (m):	2.13	
Window Area (m ²):	2.2	
Door Area (m ²):	1.9	
Radiant Slab		
Heated Fraction of the Slab:	0	
Fluid Temperature (°C):	33	
Design Months		
Heating Month	1	
Foundation Loads		
Heating Load (Watts):		2558

TYPE: 6003
LO# 95294

OPT IN-LAW


Air Infiltration Residential Load Calculator

Supplemental tool for CAN/CSA-F280

Weather Station Description				
Province:	Ontario			
Region:	Brampton			
Weather Station Location:	Open flat terrain, grass			
Anemometer height (m):	10			
Local Shielding				
Building Site:	Suburban, forest			
Walls:	Heavy			
Flue:	Heavy			
Highest Ceiling Height (m):	7.01			
Building Configuration				
Type:	Detached			
Number of Stories:	Two			
Foundation:	Full			
House Volume (m ³):	2224.8			
Air Leakage/Ventilation				
Air Tightness Type:	Energy Star Detached (2.5 ACH)			
Custom BDT Data:	ELA @ 10 Pa.	2076.8 cm ²		
	2.50	ACH @ 50 Pa		
Mechanical Ventilation (L/s):	Total Supply	Total Exhaust		
	70.8	70.8		
Flue Size				
Flue #:	#1	#2	#3	#4
Diameter (mm):	0	0	0	0
Natural Infiltration Rates				
Heating Air Leakage Rate (ACH/H):	0.234			
Cooling Air Leakage Rate (ACH/H):	0.076			

TYPE: 6003
LO# 95294

OPT IN-LAW



I MICHAEL O'ROURKE HAVE REVIEWED AND TAKE RESPONSIBILITY FOR THE DESIGN WORK AND AM QUALIFIED UNDER DIVISION C, 3.2.5 OF THE BUILDING CODE.

Michael O'Rourke
Michael O'Rourke, BCIN# 19669
HVAC DESIGNS LTD.

FURNACE 1 (F-1)
CARRIER 59SP5A-60-14
58000 BTU/H OUTPUT
3.0 TONS A/C @ 1145 cfm

FURNACE 2 (F-2)
CARRIER 59SP5A-40-12
39000 BTU/H OUTPUT
3.0 TONS A/C @ 1040 cfm

CSA-F280-12


SB-12 PERFORMANCE

HVAC LEGEND								3.		
SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION	2.		
	SUPPLY AIR GRILLE		6" SUPPLY AIR BOOT ABOVE		14"x8" RETURN AIR GRILLE		RETURN AIR STACK ABOVE	1.	REVISED TO PERFORMANCE PATH	APR/2022
	SUPPLY AIR GRILLE 6" BOOT		SUPPLY AIR STACK FROM 2nd FLOOR		30"x8" RETURN AIR GRILLE		RETURN AIR STACK 2nd FLOOR	No.	Description	Date
	SUPPLY AIR BOOT ABOVE		6" SUPPLY AIR STACK 2nd FLOOR		FRA- FLOOR RETURN AIR GRILLE		REDUCER	REVISIONS		

ALL DRAWINGS, CALCULATIONS AND SPECIFICATIONS ARE THE PROPERTY OF HVAC DESIGNS LTD.© AND MAY NOT BE REPRODUCED, MODIFIED OR ALTERED WITHOUT EXPRESSED WRITTEN CONSENT. THE DRAWINGS ARE DATED AND USE OF THESE DRAWINGS AFTER ONE YEAR FROM THE DATED NOTED IS NOT AUTHORIZED. CONTRACTOR SHALL CHECK ALL CONDITIONS BEFORE PROCEEDING WITH WORK. LATEST MUNICIPAL APPROVED DRAWINGS ONLY TO BE USED DURING INSTALLATION OF HEATING SYSTEM. HVAC DESIGNS LTD. IS NOT LIABLE FOR ANY CLAIMS ARISING FROM UNAUTHORIZED USE OF THE DRAWINGS OR FROM ANY CHANGES TO ACCEPTED STANDARDS AND/OR THE ONTARIO BUILDING CODE.

Client		 375 Finley Ave. Suite 202 - Ajax, Ontario L1S 2E2 Tel. 905.619.2300 - 905.420.5300 Fax 905.619.2375 Email: info@hvacdesigns.ca Web: www.hvacdesigns.ca Specializing in Residential Mechanical Design Services Installation to comply with the latest Ontario Building Code. All supply branch outlets shall be equipped with a manual balancing damper. Ductwork which passes through the garage or unheated spaces shall be adequately insulated and be gas-proofed.					Sheet Title	
ROYAL PINE HOMES							BASEMENT HEATING LAYOUT	
Project Name							Date	MAR/2022
VALES OF HUMBER SOUTH BRAMPTON, ONTARIO							Scale	3/16" = 1'-0"
OPT IN-LAW							BCIN# 19669	
6003							LO#	95294
5239 sqft								

	S/A	R/A	FANS
2ND	21	6	6
1ST	20	5	4
BAS	8	1	0



I MICHAEL O'ROURKE HAVE REVIEWED AND TAKE RESPONSIBILITY FOR THE DESIGN WORK AND AM QUALIFIED UNDER DIVISION C, 3.2.5 OF THE BUILDING CODE.

Michael O'Rourke
Michael O'Rourke, BCIN# 19669
HVAC DESIGNS LTD.


CSA-F280-12

SB-12 PERFORMANCE

HVAC LEGEND								3.		
SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION	2.		
	SUPPLY AIR GRILLE		6" SUPPLY AIR BOOT ABOVE		14"x8" RETURN AIR GRILLE		RETURN AIR STACK ABOVE	1.	REVISED TO PERFORMANCE PATH	APR/2022
	SUPPLY AIR GRILLE 6" BOOT		SUPPLY AIR STACK FROM 2nd FLOOR		30"x8" RETURN AIR GRILLE		RETURN AIR STACK 2nd FLOOR	No.	Description	Date
	SUPPLY AIR BOOT ABOVE		6" SUPPLY AIR STACK 2nd FLOOR		FRA- FLOOR RETURN AIR GRILLE		REDUCER	REVISIONS		

ALL DRAWINGS, CALCULATIONS AND SPECIFICATIONS ARE THE PROPERTY OF HVAC DESIGNS LTD.© AND MAY NOT BE REPRODUCED, MODIFIED OR ALTERED WITHOUT EXPRESSED WRITTEN CONSENT. THE DRAWINGS ARE DATED AND USE OF THESE DRAWINGS AFTER ONE YEAR FROM THE DATED NOTED IS NOT AUTHORIZED. CONTRACTOR SHALL CHECK ALL CONDITIONS BEFORE PROCEEDING WITH WORK. LATEST MUNICIPAL APPROVED DRAWINGS ONLY TO BE USED DURING INSTALLATION OF HEATING SYSTEM. HVAC DESIGNS LTD. IS NOT LIABLE FOR ANY CLAIMS ARISING FROM UNAUTHORIZED USE OF THE DRAWINGS OR FROM ANY CHANGES TO ACCEPTED STANDARDS AND/OR THE ONTARIO BUILDING CODE.

Client		 375 Finley Ave. Suite 202 - Ajax, Ontario L1S 2E2 Tel. 905.619.2300 - 905.420.5300 Fax 905.619.2375 Email: info@hvacdesigns.ca Web: www.hvacdesigns.ca Specializing in Residential Mechanical Design Services Installation to comply with the latest Ontario Building Code. All supply branch outlets shall be equipped with a manual balancing damper. Ductwork which passes through the garage or unheated spaces shall be adequately insulated and be gas-proofed.	Sheet Title																			
ROYAL PINE HOMES			FIRST FLOOR HEATING LAYOUT																			
Project Name			Date MAR/2022																			
VALES OF HUMBER SOUTH BRAMPTON, ONTARIO			Scale 3/16" = 1'-0"																			
OPT IN-LAW 6003		5239 sqft	BCIN# 19669																			
			LO# 95294																			
			<table><tr><td></td><td>S/A</td><td>R/A</td><td>FANS</td></tr><tr><td>2ND</td><td>21</td><td>6</td><td>6</td></tr><tr><td>1ST</td><td>20</td><td>5</td><td>4</td></tr><tr><td>BAS</td><td>8</td><td>1</td><td>0</td></tr></table>					S/A	R/A	FANS	2ND	21	6	6	1ST	20	5	4	BAS	8	1	0
	S/A	R/A	FANS																			
2ND	21	6	6																			
1ST	20	5	4																			
BAS	8	1	0																			



I MICHAEL O'ROURKE HAVE REVIEWED AND TAKE RESPONSIBILITY FOR THE DESIGN WORK AND AM QUALIFIED UNDER DIVISION C, 3.2.5 OF THE BUILDING CODE.

Michael O'Rourke
Michael O'Rourke, BCIN# 19669
HVAC DESIGNS LTD.

CSA-F280-12

SB-12 PERFORMANCE

HVAC LEGEND								3.		
SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION	2.		
	SUPPLY AIR GRILLE		6" SUPPLY AIR BOOT ABOVE		14"x8" RETURN AIR GRILLE		RETURN AIR STACK ABOVE	1.	REVISED TO PERFORMANCE PATH	APR/2022
	SUPPLY AIR GRILLE 6" BOOT		SUPPLY AIR STACK FROM 2nd FLOOR		30"x8" RETURN AIR GRILLE		RETURN AIR STACK 2nd FLOOR	No.	Description	Date
	SUPPLY AIR BOOT ABOVE		6" SUPPLY AIR STACK 2nd FLOOR		FRA- FLOOR RETURN AIR GRILLE		REDUCER	REVISIONS		

ALL DRAWINGS, CALCULATIONS AND SPECIFICATIONS ARE THE PROPERTY OF HVAC DESIGNS LTD.© AND MAY NOT BE REPRODUCED, MODIFIED OR ALTERED WITHOUT EXPRESSED WRITTEN CONSENT. THE DRAWINGS ARE DATED AND USE OF THESE DRAWINGS AFTER ONE YEAR FROM THE DATED NOTED IS NOT AUTHORIZED. CONTRACTOR SHALL CHECK ALL CONDITIONS BEFORE PROCEEDING WITH WORK. LATEST MUNICIPAL APPROVED DRAWINGS ONLY TO BE USED DURING INSTALLATION OF HEATING SYSTEM. HVAC DESIGNS LTD. IS NOT LIABLE FOR ANY CLAIMS ARISING FROM UNAUTHORIZED USE OF THE DRAWINGS OR FROM ANY CHANGES TO ACCEPTED STANDARDS AND/OR THE ONTARIO BUILDING CODE.

Client		 375 Finley Ave. Suite 202 - Ajax, Ontario L1S 2E2 Tel. 905.619.2300 - 905.420.5300 Fax 905.619.2375 Email: info@hvacdesigns.ca Web: www.hvacdesigns.ca Specializing in Residential Mechanical Design Services Installation to comply with the latest Ontario Building Code. All supply branch outlets shall be equipped with a manual balancing damper. Ductwork which passes through the garage or unheated spaces shall be adequately insulated and be gas-proofed.	Sheet Title			
ROYAL PINE HOMES			SECOND FLOOR HEATING LAYOUT			
Project Name			Date MAR/2022			
VALES OF HUMBER SOUTH BRAMPTON, ONTARIO			Scale 3/16" = 1'-0"			
OPT IN-LAW 6003			BCIN# 19669			
5239 sqft			LO# 95294			

	S/A	R/A	FANS
2ND	21	6	6
1ST	20	5	4
BAS	8	1	0