


Schedule 1: Designer Information

Use one form for each individual who reviews and takes responsibility for design activities with respect to the project.

A. Project Information			
Building number, street name		Unit no.	Lot/con.
Municipality BRAMPTON	Postal code	Plan number/ other description	
B. Individual who reviews and takes responsibility for design activities			
Name MICHAEL O'ROURKE		Firm HVAC DESIGNS LTD.	
Street address 375 FINLEY AVE		Unit no. 202	Lot/con. N/A
Municipality AJAX	Postal code L1S 2E2	Province ONTARIO	E-mail info@hvacdsgns.ca
Telephone number (905) 619-2300	Fax number (905) 619-2375	Cell number	
C. Design activities undertaken by individual identified in Section B. [Building Code Table 3.5.2.1 OF Division C]			
☐ House ☐ Small Buildings ☐ Large Buildings ☐ Complex Buildings			
☒ HVAC – House ☐ Building Services ☐ Detection, Lighting and Power ☐ Fire Protection			
☐ Building Structural ☐ Plumbing – House ☐ Plumbing – All Buildings ☐ On-site Sewage Systems			
Description of designer's work HEAT LOSS / GAIN CALCULATIONS DUCT SIZING RESIDENTIAL MECHANICAL VENTILATION DESIGN SUMMARY RESIDENTIAL SYSTEM DESIGN per CSA-F280-12		Model: 5008 OPT IN-LAW Project: VALES OF HUMBER SOUTH	
D. Declaration of Designer			
I, <u>MICHAEL O'ROURKE</u> (print name)		declare that (choose one as appropriate):	
☐ I review and take responsibility for the design work on behalf of a firm registered under subsection 3.2.4. of Division C, of the Building Code. I am qualified, and the firm is registered, in the appropriate classes/categories. Individual BCIN: _____ Firm BCIN: _____			
☒ I review and take responsibility for the design and am qualified in the appropriate category as an "other designer" under subsection 3.2.5. of Division C, of the Building Code. Individual BCIN: <u>19669</u> Basis for exemption from registration and qualification: <u>O.B.C SENTENCE 3.2.4.1 (4)</u>			
☐ The design work is exempt from the registration and qualification requirements of the Building Code. Basis for exemption from registration and qualification: _____			
I certify that:			
1. The information contained in this schedule is true to the best of my knowledge.			
2. I have submitted this application with the knowledge and consent of the firm.			
July 11, 2024 Date		 Signature of Designer	

NOTE:

- For the purposes of this form, "individual" means the "person" referred to in Clause 3.2.4.7(1) d) of Division C, Article 3.2.5.1. of Division C, and all other persons who are exempt from qualification under Subsections 3.2.4. and 3.2.5. of Division C.
- Schedule 1 is not required to be completed by a holder of a license, temporary license, or a certificate of authorization, issued by the Ontario Association of Architects. Schedule 1 is also not required to be completed by a holder of a license to practise, a limited license to practise, or a certificate of authorization, issued by the Association of Professional Engineers of Ontario.

Application for a Permit Construct or Demolish – Effective January 1, 2015

[illegible]

TOTAL HEAT GAIN BTU/H:	53671	TONS: 4.47	LOSS DUE TO VENTILATION LOAD BTU/H: 6010	STRUCTURAL HEAT LOSS: 64891	TOTAL COMBINED HEAT LOSS BTU/H: 70902
------------------------	-------	------------	--	-----------------------------	---------------------------------------

Michael Lounsbury

SITE NAME: VALES OF HUMBER SOUTH				OPT IN-LAW		DATE Jul-24		WINTER NATURAL AIR CHANGE RATE 0.234		HEAT LOSS AT °F. 74		CSA-F280-12	
BUILDER: ROYAL PINE HOMES				TYPE: 5008		GFA: 4382		LO# 95286		SUMMER NATURAL AIR CHANGE RATE 0.076		HEAT GAIN ΔT °F. 11	
ROOM USE	EXP. WALL	CLG. HT.	PR/ST	ENS	BED-2	BED-3	BED-4	BATH-2	BED-5	BATH-3	SHARED		
			59	24	21	16	40	10	16	17	10		
			9	9	9	10	10	9	9	9	9		
FACTORS													
GRS.WALL AREA	LOSS	GAIN	531	216	189	160	400	90	144	153	90		
GLAZING	LOSS	GAIN		LOSS	GAIN	LOSS	GAIN	LOSS	GAIN	LOSS	GAIN	LOSS	GAIN
NORTH	20.8	15.5	9	187	139	9	187	139	0	0	0	0	0
EAST	20.8	41.0	0	0	0	0	0	0	0	0	0	0	0
SOUTH	20.8	24.4	9	187	220	0	0	0	24	499	585	0	0
WEST	20.8	41.0	52	1080	2134	18	374	739	0	0	0	0	0
SKYLT.	34.1	100.3	0	0	0	0	0	0	0	0	0	0	0
DOORS	24.7	3.7	0	0	0	0	0	0	0	0	0	0	0
NET EXPOSED WALL	3.5	0.5	461	1598	237	189	655	97	165	572	85	121	420
NET EXPOSED BSMT WALL ABOVE GR	3.5	0.5	0	0	0	0	0	0	0	0	0	0	0
EXPOSED CLG	1.3	0.6	684	857	381	143	179	80	441	553	246	344	431
NO ATTIC EXPOSED CLG	2.7	1.2	0	0	0	0	0	0	0	0	0	0	0
EXPOSED FLOOR	2.5	0.4	0	0	0	0	0	0	0	0	0	0	0
BASEMENT/CRAWL HEAT LOSS			0	0	0	0	0	0	0	0	0	0	0
SLAB ON GRADE HEAT LOSS			0	0	0	0	0	0	0	0	0	0	0
SUBTOTAL HT LOSS			3910		1395		1623		692		1316		1035
SUB TOTAL HT GAIN				3111		1055		702		236		825	
LEVEL FACTOR / MULTIPLIER	0.20	0.25			0.20	0.25		0.20	0.25		0.20	0.25	
AIR CHANGE HEAT LOSS			983		351		408		174		331		260
AIR CHANGE HEAT GAIN				161		55		36		12		43	
DUCT LOSS			0		0		0		87		0		130
DUCT GAIN				0		0		0		25		0	
HEAT GAIN PEOPLE	240		2		480		0		0		1		240
HEAT GAIN APPLIANCES/LIGHTS					918		0		0				918
TOTAL HT LOSS BTU/H			4893		1746		2031		953		1646		1425
TOTAL HT GAIN x 1.3 BTU/H				6072		1443		2465		356		2634	

ROOM USE	EXP. WALL	CLG. HT.											
FACTORS													
GRS.WALL AREA	LOSS	GAIN											
GLAZING													
NORTH	20.8	15.5											
EAST	20.8	41.0											
SOUTH	20.8	24.4											
WEST	20.8	41.0											
SKYLT.	34.1	100.3											
DOORS	24.7	3.7											
NET EXPOSED WALL	3.5	0.5											
NET EXPOSED BSMT WALL ABOVE GR	3.5	0.5											
EXPOSED CLG	1.3	0.6											
NO ATTIC EXPOSED CLG	2.7	1.2											
EXPOSED FLOOR	2.5	0.4											
BASEMENT/CRAWL HEAT LOSS													
SLAB ON GRADE HEAT LOSS													
SUBTOTAL HT LOSS													
SUB TOTAL HT GAIN													
LEVEL FACTOR / MULTIPLIER													
AIR CHANGE HEAT LOSS													
AIR CHANGE HEAT GAIN													
DUCT LOSS													
DUCT GAIN													
HEAT GAIN PEOPLE	240												
HEAT GAIN APPLIANCES/LIGHTS													
TOTAL HT LOSS BTU/H													
TOTAL HT GAIN x 1.3 BTU/H													

TOTAL HEAT GAIN BTU/H: 53671 TONS: 4.47 LOSS DUE TO VENTILATION LOAD BTU/H: 6010 STRUCTURAL HEAT LOSS: 64891 TOTAL COMBINED HEAT LOSS BTU/H: 70902

SITE NAME: VALES OF HUMBER SOUTH
BUILDER: ROYAL PINE HOMES

OPT IN-LAW
TYPE: 5008

DATE: Jul-24

GFA: 4382 LO# 95286

FURNACE 1

HEATING CFM 975
TOTAL HEAT LOSS 44,262
AIR FLOW RATE CFM 22.03

COOLING CFM 975
TOTAL HEAT GAIN 29,033
AIR FLOW RATE CFM 33.58

**FACTORY
INSTALLED**

furnace pressure 0.6
furnace filter 0
a/c coil pressure 0.21
available pressure for s/a & r/a 0.39

**FURNACE HEAT LOSS +
HRV / ERV HEAT LOSS
= 47267 BTUH**
CARRIER
59SC6A060M17--16
FAN SPEED LOW 0
MEDLOW 790
MEDIUM 975
MEDIUM HIGH 1140
HIGH 1300

AFUE = 97 %
INPUT (BTU/H) = 60,000
OUTPUT (BTU/H) = **58,000**

DESIGN CFM = **975**
CFM @ .6" E.S.P.

TEMPERATURE RISE 55 °F

RUN COUNT	4th	3rd	2nd	1st	Bas
S/A	0	0	0	15	7
R/A	0	0	0	3	1

All S/A diffusers 4"x10" unless noted otherwise on layout.

All S/A runs 5"Ø unless noted otherwise on layout.

RUN #	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	21	22	23	24
ROOM NAME	IN-LAW	IN-LAW	GREAT	GREAT	KIT	KIT	KIT	DIN	LIV	LIV	LIV	FOY	FOY	LAUN	I-ENS	BAS	BAS	BAS	BAS
RM LOSS MBH.	1.04	1.04	1.42	1.42	1.64	1.64	1.64	1.44	1.18	1.18	1.18	2.10	2.10	3.60	0.50	3.02	3.02	3.02	3.02
CFM PER RUN HEAT	23	23	31	31	36	36	36	32	26	26	26	46	46	79	11	67	67	67	67
RM GAIN MBH.	1.84	1.84	2.03	2.03	2.28	2.28	2.28	2.17	1.66	1.66	1.66	1.75	1.75	2.00	0.21	0.23	0.23	0.23	0.23
CFM PER RUN COOLING	62	62	68	68	77	77	77	73	56	56	56	59	59	67	7	8	8	8	8
ADJUSTED PRESSURE	0.19	0.19	0.19	0.19	0.19	0.19	0.19	0.19	0.19	0.19	0.19	0.19	0.19	0.19	0.19	0.19	0.19	0.19	0.19
ACTUAL DUCT LGH.	47	41	39	25	24	30	20	31	48	43	38	44	39	42	36	23	31	37	26
EQUIVALENT LENGTH	160	150	160	140	110	110	100	100	120	110	100	130	100	160	100	100	140	100	110
TOTAL EFFECTIVE LENGTH	207	191	199	165	134	140	120	131	168	153	138	174	139	202	136	123	171	137	136
ADJUSTED PRESSURE	0.09	0.1	0.1	0.12	0.14	0.14	0.16	0.15	0.11	0.13	0.14	0.11	0.14	0.1	0.14	0.16	0.11	0.14	0.14
ROUND DUCT SIZE	5	5	5	5	5	5	5	5	4	4	4	5	5	5	4	5	5	5	5
HEATING VELOCITY (ft/min)	169	169	228	228	264	264	264	235	298	298	298	338	338	580	126	492	492	492	492
COOLING VELOCITY (ft/min)	455	455	499	499	565	565	565	536	642	642	642	433	433	492	80	59	59	59	59
OUTLET GRILL SIZE	3X10	3X10	3X10	3X10	3X10	3X10	3X10	3X10	3X10	3X10	3X10	3X10	3X10	3X10	3X10	3X10	3X10	3X10	3X10
TRUNK	A	A	A	A	A	A	B	D	C	C	C	C	D	B	B	B	A	B	B

RUN #	25	26	27
ROOM NAME	BAS	BAS	BAS
RM LOSS MBH.	3.02	3.02	3.02
CFM PER RUN HEAT	67	67	67
RM GAIN MBH.	0.23	0.23	0.23
CFM PER RUN COOLING	8	8	8
ADJUSTED PRESSURE	0.19	0.19	0.19
ACTUAL DUCT LGH.	27	26	39
EQUIVALENT LENGTH	140	100	120
TOTAL EFFECTIVE LENGTH	167	126	159
ADJUSTED PRESSURE	0.12	0.15	0.12
ROUND DUCT SIZE	5	5	5
HEATING VELOCITY (ft/min)	492	492	492
COOLING VELOCITY (ft/min)	59	59	59
OUTLET GRILL SIZE	3X10	3X10	3X10
TRUNK	D	D	C

SUPPLY AIR TRUNK SIZE

	TRUNK	STATIC	ROUND	RECT			VELOCITY		TRUNK	STATIC	ROUND	RECT			VELOCITY
	CFM	PRESS.	DUCT	DUCT			(ft/min)		CFM	PRESS.	DUCT	DUCT			(ft/min)
TRUNK A	247	0.09	8.1	12	x	8	371	TRUNK G	0	0.00	0	0	x	8	0
TRUNK B	574	0.09	11.1	16	x	8	646	TRUNK H	0	0.00	0	0	x	8	0
TRUNK C	191	0.11	7	8	x	8	430	TRUNK I	0	0.00	0	0	x	8	0
TRUNK D	403	0.11	9.2	12	x	8	605	TRUNK J	0	0.00	0	0	x	8	0
TRUNK E	0	0.00	0	0	x	8	0	TRUNK K	0	0.00	0	0	x	8	0
TRUNK F	0	0.00	0	0	x	8	0	TRUNK L	0	0.00	0	0	x	8	0

RETURN AIR TRUNK SIZE

	TRUNK	STATIC	ROUND	RECT		VELOCITY	
	CFM	PRESS.	DUCT	DUCT		(ft/min)	
TRUNK O	0	0.08	0	0	x	8	0
TRUNK P	0	0.08	0	0	x	8	0
TRUNK Q	0	0.08	0	0	x	8	0
TRUNK R	0	0.08	0	0	x	8	0
TRUNK S	0	0.08	0	0	x	8	0
TRUNK T	0	0.08	0	0	x	8	0
TRUNK U	0	0.08	0	0	x	8	0
TRUNK V	0	0.08	0	0	x	8	0
TRUNK W	0	0.08	0	0	x	8	0
TRUNK X	975	0.08	13.9	26	x	8	675
TRUNK Y	205	0.08	7.7	8	x	8	461
TRUNK Z	0	0.08	0	0	x	8	0
DROP	975	0.08	13.9	24	x	10	585

RETURN AIR #	1	2	3												BR
AIR VOLUME	205	360	360	0	0	0	0	0	0	0	0	0	0	0	50
PLENUM PRESSURE	0.17	0.17	0.17	0.17	0.17	0.17	0.17	0.17	0.17	0.17	0.17	0.17	0.17	0.17	0.17
ACTUAL DUCT LGH.	43	23	23	1	1	1	1	1	1	1	1	1	1	1	18
EQUIVALENT LENGTH	130	145	150	0	0	0	0	0	0	0	0	0	0	0	190
TOTAL EFFECTIVE LH	173	168	173	1	1	1	1	1	1	1	1	1	1	1	208
ADJUSTED PRESSURE	0.10	0.10	0.10	16.72	16.72	16.72	16.72	16.72	16.72	16.72	16.72	16.72	16.72	16.72	0.08
ROUND DUCT SIZE	7.3	9	9	0	0	0	0	0	0	0	0	0	0	0	4.6
INLET GRILL SIZE	8	8	8	0	0	0	0	0	0	0	0	0	0	0	8
	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X
INLET GRILL SIZE	14	30	30	0	0	0	0	0	0	0	0	0	0	0	14

SITE NAME: VALES OF HUMBER SOUTH
BUILDER: ROYAL PINE HOMES

OPT IN-LAW
TYPE: 5008

DATE: Jul-24

GFA: 4382 LO# 95286

FURNACE 2

HEATING CFM 770 COOLING CFM 770
TOTAL HEAT LOSS 20,629 TOTAL HEAT GAIN 24,192
AIR FLOW RATE CFM 37.33 AIR FLOW RATE CFM 31.83

**FACTORY
INSTALLED**

furnace pressure 0.6
furnace filter 0
a/c coil pressure 0.26
available pressure for s/a & r/a 0.34

**FURNACE HEAT LOSS +
HRV / ERV HEAT LOSS
= 23634 BTUH**
CARRIER
59SC6A026M14--10
26
FAN SPEED LOW 0
MEDLOW 545
MEDIUM 770
MEDIUM HIGH 0
HIGH 0

AFUE = 96 %
INPUT (BTU/H) = 26,000
OUTPUT (BTU/H) = **25,000**

DESIGN CFM = **770**
CFM @ .6" E.S.P.

TEMPERATURE RISE 30 °F

RUN COUNT	4th	3rd	2nd	1st	Bas
S/A	0	0	15	0	0
R/A	0	0	6	0	0

All S/A diffusers 4"x10" unless noted otherwise on layout.

All S/A runs 5"Ø unless noted otherwise on layout.

RUN #	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15
ROOM NAME	PR/ST	PR/ST	PR/ST	ENS	BED-2	BED-2	BATH-2	BED-3	BED-3	BATH-3	BED-4	BED-4	SHARED	BED-5	BED-5
RM LOSS MBH.	1.63	1.63	1.63	1.75	1.02	1.02	0.95	1.84	1.84	1.42	1.81	1.81	0.63	0.82	0.82
CFM PER RUN HEAT	61	61	61	65	38	38	36	69	69	53	68	68	23	31	31
RM GAIN MBH.	2.02	2.02	2.02	1.44	1.23	1.23	0.36	2.35	2.35	1.07	2.63	2.63	0.18	1.32	1.32
CFM PER RUN COOLING	64	64	64	46	39	39	11	75	75	34	84	84	6	42	42
ADJUSTED PRESSURE	0.17	0.17	0.17	0.17	0.17	0.17	0.17	0.17	0.17	0.17	0.16	0.16	0.17	0.17	0.17
ACTUAL DUCT LGH.	41	69	53	58	56	54	59	58	62	68	62	59	57	67	31
EQUIVALENT LENGTH	160	150	140	160	170	190	140	140	150	110	170	150	110	150	160
TOTAL EFFECTIVE LENGTH	201	219	193	218	226	244	199	198	212	178	232	209	167	217	191
ADJUSTED PRESSURE	0.08	0.08	0.09	0.08	0.07	0.07	0.08	0.08	0.08	0.09	0.07	0.08	0.1	0.08	0.09
ROUND DUCT SIZE	5	5	5	5	5	5	4	6	6	5	6	6	4	5	4
HEATING VELOCITY (ft/min)	448	448	448	477	279	279	413	352	352	389	347	347	264	228	356
COOLING VELOCITY (ft/min)	470	470	470	338	286	286	126	382	382	250	428	428	69	308	482
OUTLET GRILL SIZE	3X10	3X10	3X10	3X10	3X10	3X10	3X10	4X10	4X10	3X10	4X10	4X10	3X10	3X10	3X10
TRUNK	C	C	C	C	C	C	B	A	A	B	A	A	B	B	B

RUN #	ROOM NAME	RM LOSS MBH.	CFM PER RUN HEAT	RM GAIN MBH.	CFM PER RUN COOLING	ADJUSTED PRESSURE	ACTUAL DUCT LGH.	EQUIVALENT LENGTH	TOTAL EFFECTIVE LENGTH	ADJUSTED PRESSURE	ROUND DUCT SIZE	HEATING VELOCITY (ft/min)	COOLING VELOCITY (ft/min)	OUTLET GRILL SIZE	TRUNK
-------	-----------	--------------	------------------	--------------	---------------------	-------------------	------------------	-------------------	------------------------	-------------------	-----------------	---------------------------	---------------------------	-------------------	-------

SUPPLY AIR TRUNK SIZE

	TRUNK	STATIC	ROUND	RECT			VELOCITY		TRUNK	STATIC	ROUND	RECT			VELOCITY
	CFM	PRESS.	DUCT	DUCT			(ft/min)		CFM	PRESS.	DUCT	DUCT			(ft/min)
TRUNK A	274	0.07	8.9	10	x	8	493	TRUNK G	0	0.00	0	0	x	8	0
TRUNK B	448	0.07	10.7	14	x	8	576	TRUNK H	0	0.00	0	0	x	8	0
TRUNK C	324	0.07	9.5	10	x	8	583	TRUNK I	0	0.00	0	0	x	8	0
TRUNK D	0	0.00	0	0	x	8	0	TRUNK J	0	0.00	0	0	x	8	0
TRUNK E	0	0.00	0	0	x	8	0	TRUNK K	0	0.00	0	0	x	8	0
TRUNK F	0	0.00	0	0	x	8	0	TRUNK L	0	0.00	0	0	x	8	0

RETURN AIR TRUNK SIZE

	TRUNK	STATIC	ROUND	RECT		VELOCITY	
	CFM	PRESS.	DUCT	DUCT		(ft/min)	
TRUNK O	0	0.05	0	0	x	8	0
TRUNK P	0	0.05	0	0	x	8	0
TRUNK Q	0	0.05	0	0	x	8	0
TRUNK R	0	0.05	0	0	x	8	0
TRUNK S	0	0.05	0	0	x	8	0
TRUNK T	0	0.05	0	0	x	8	0
TRUNK U	0	0.05	0	0	x	8	0
TRUNK V	0	0.05	0	0	x	8	0
TRUNK W	0	0.05	0	0	x	8	0
TRUNK X	770	0.05	14.3	24	x	8	578
TRUNK Y	375	0.05	10.9	14	x	8	482
TRUNK Z	315	0.05	10.2	12	x	8	473
DROP	770	0.05	14.3	24	x	10	462

RETURN AIR #	1	2	3	4	5	6									BR
AIR VOLUME	230	85	85	75	85	215	0	0	0	0	0	0	0	0	0
PLENUM PRESSURE	0.14	0.14	0.14	0.14	0.14	0.14	0.14	0.14	0.14	0.14	0.14	0.14	0.14	0.14	0.14
ACTUAL DUCT LGH.	62	57	61	82	66	64	1	1	1	1	1	1	1	1	1
EQUIVALENT LENGTH	180	175	175	220	185	215	0	0	0	0	0	0	0	0	0
TOTAL EFFECTIVE LH	242	232	236	302	251	279	1	1	1	1	1	1	1	1	1
ADJUSTED PRESSURE	0.06	0.06	0.06	0.05	0.06	0.05	14.32	14.32	14.32	14.32	14.32	14.32	14.32	14.32	14.32
ROUND DUCT SIZE	8.7	6	6	6	6	8.9	0	0	0	0	0	0	0	0	0
INLET GRILL SIZE	8	8	8	8	8	8	0	0	0	0	0	0	0	0	0
	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X
INLET GRILL SIZE	30	14	14	14	14	30	0	0	0	0	0	0	0	0	0

TYPE: 5008
SITE NAME: VALES OF HUMBER SOUTH

LO # 95286
OPT IN-LAW

RESIDENTIAL MECHANICAL VENTILATION DESIGN SUMMARY

COMBUSTION APPLIANCES		9.32.3.1(1)
a)	☒ Direct vent (sealed combustion) only	
b)	☐ Positive venting induced draft (except fireplaces)	
c)	☐ Natural draft, B-vent or induced draft gas fireplace	
d)	☐ Solid Fuel (including fireplaces)	
e)	☐ No Combustion Appliances	

HEATING SYSTEM	
☒ Forced Air	☐ Non Forced Air
☐ Electric Space Heat	

HOUSE TYPE		9.32.1(2)
☒ I	Type a) or b) appliance only, no solid fuel	
☐ II	Type I except with solid fuel (including fireplaces)	
☐ III	Any Type c) appliance	
☐ IV	Type I, or II with electric space heat	
☐	Other: Type I, II or IV no forced air	

SYSTEM DESIGN OPTIONS		O.N.H.W.P.
☐ 1	Exhaust only/Forced Air System	
☐ 2	HRV with Ducting/Forced Air System	
☒ 3	HRV Simplified/connected to forced air system	
☐ 4	HRV with Ducting/non forced air system	
☐	Part 6 Design	

TOTAL VENTILATION CAPACITY		9.32.3.3(1)
Basement + Master Bedroom	<u>2</u> @ 21.2 cfm <u>42.4</u> cfm	
Other Bedrooms	<u>5</u> @ 10.6 cfm <u>53</u> cfm	
Kitchen & Bathrooms	<u>7</u> @ 10.6 cfm <u>74.2</u> cfm	
Other Rooms	<u>5</u> @ 10.6 cfm <u>53.0</u> cfm	
Table 9.32.3.A.	TOTAL <u>222.6</u> cfm	

PRINCIPAL VENTILATION CAPACITY REQUIRED		9.32.3.4.(1)
6 Bedrooms		
As Per Ashrea 62.2 Dwelling- Unit Ventilation		
4.1.1 Total Ventilation Rate		
$Q_{tot}=0.03A_{floor}+7.5(N_{br}+1)$		
TOTAL 184 cfm		

SUPPLEMENTAL VENTILATION CAPACITY		9.32.3.5.
Total Ventilation Capacity	<u>222.6</u>	cfm
Less Principal Ventil. Capacity	<u>150</u>	cfm
Required Supplemental Capacity	<u>72.6</u>	cfm

PRINCIPAL EXHAUST FAN CAPACITY	
Model: VANEE V150H	Location: BSMT
<u>150.0</u> cfm	☒ HVI Approved

PRINCIPAL EXHAUST HEAT LOSS CALCULATION				
CFM	ΔT °F	FACTOR	% LOSS	
150.0 CFM	X 74 F	X 1.08	X	0.25

SUPPLEMENTAL FANS		BY INSTALLING CONTRACTOR		
Location	Model	cfm	HVI	Sones
ENS	BY INSTALLING CONTRACTOR	50	☒	3.5
BATH-2	BY INSTALLING CONTRACTOR	50	☒	3.5
SHARED	BY INSTALLING CONTRACTOR	50	☒	3.5
BATH-3	BY INSTALLING CONTRACTOR	50	☒	3.5

HEAT RECOVERY VENTILATOR		9.32.3.11.
Model: VANEE V150H	INSTALL 2 HRV / ERV's	
<u>150</u> cfm high	<u>35</u> cfm low	
<u>75</u> % Sensible Efficiency @ 32 deg F (0 deg C)	☒ HVI Approved	

LOCATION OF INSTALLATION	
Lot:	Concession
Township	Plan:
Address	
Roll #	Building Permit #

BUILDER: ROYAL PINE HOMES	
Name:	
Address:	
City:	
Telephone #:	Fax #:

INSTALLING CONTRACTOR	
Name:	
Address:	
City:	
Telephone #:	Fax #:

DESIGNER CERTIFICATION	
I hereby certify that this ventilation system has been designed in accordance with the Ontario Building Code.	
Name:	HVAC Designs Ltd.
Signature:	<i>Michael O'Rourke</i>
HRAI #	001820
Date:	July-24

CSA F280-12 Residential Heat Loss and Heat Gain Calculations																																																												
Formula Sheet (For Air Leakage / Ventilation Calculation)																																																												
LO#: 95286	Model: 5008	Builder: ROYAL PINE HOMES	Date: 7/11/2024																																																									
Volume Calculation			Air Change & Delta T Data																																																									
House Volume <table border="1" style="width:100%; border-collapse: collapse; margin-top: 5px;"> <thead> <tr> <th>Level</th> <th>Floor Area (ft²)</th> <th>Floor Height (ft)</th> <th>Volume (ft³)</th> </tr> </thead> <tbody> <tr><td>Bsmt</td><td>2059</td><td>10</td><td>20590</td></tr> <tr><td>First</td><td>2059</td><td>11</td><td>22649</td></tr> <tr><td>Second</td><td>2398</td><td>9</td><td>21582</td></tr> <tr><td>Third</td><td>0</td><td>9</td><td>0</td></tr> <tr><td>Fourth</td><td>0</td><td>9</td><td>0</td></tr> <tr><td colspan="3" style="text-align: right;">Total:</td><td>64,821.0 ft³</td></tr> <tr><td colspan="3" style="text-align: right;">Total:</td><td>1835.5 m³</td></tr> </tbody> </table>			Level	Floor Area (ft²)	Floor Height (ft)	Volume (ft³)	Bsmt	2059	10	20590	First	2059	11	22649	Second	2398	9	21582	Third	0	9	0	Fourth	0	9	0	Total:			64,821.0 ft³	Total:			1835.5 m³	<table border="1" style="width:100%; border-collapse: collapse; margin-top: 5px;"> <tr> <td style="width: 70%;">WINTER NATURAL AIR CHANGE RATE</td> <td style="width: 30%; text-align: center;">0.234</td> </tr> <tr> <td>SUMMER NATURAL AIR CHANGE RATE</td> <td style="text-align: center;">0.076</td> </tr> </table> <table border="1" style="width:100%; border-collapse: collapse; margin-top: 5px;"> <tr> <th colspan="5" style="text-align: center;">Design Temperature Difference</th> </tr> <tr> <th></th> <th>Tin °C</th> <th>Tout °C</th> <th>ΔT °C</th> <th>ΔT °F</th> </tr> <tr> <td>Winter DTDh</td> <td style="text-align: center;">22</td> <td style="text-align: center;">-19</td> <td style="text-align: center;">41</td> <td style="text-align: center;">74</td> </tr> <tr> <td>Summer DTDc</td> <td style="text-align: center;">24</td> <td style="text-align: center;">30</td> <td style="text-align: center;">6</td> <td style="text-align: center;">11</td> </tr> </table>		WINTER NATURAL AIR CHANGE RATE	0.234	SUMMER NATURAL AIR CHANGE RATE	0.076	Design Temperature Difference						Tin °C	Tout °C	ΔT °C	ΔT °F	Winter DTDh	22	-19	41	74	Summer DTDc	24	30	6	11
Level	Floor Area (ft²)	Floor Height (ft)	Volume (ft³)																																																									
Bsmt	2059	10	20590																																																									
First	2059	11	22649																																																									
Second	2398	9	21582																																																									
Third	0	9	0																																																									
Fourth	0	9	0																																																									
Total:			64,821.0 ft³																																																									
Total:			1835.5 m³																																																									
WINTER NATURAL AIR CHANGE RATE	0.234																																																											
SUMMER NATURAL AIR CHANGE RATE	0.076																																																											
Design Temperature Difference																																																												
	Tin °C	Tout °C	ΔT °C	ΔT °F																																																								
Winter DTDh	22	-19	41	74																																																								
Summer DTDc	24	30	6	11																																																								
5.2.3.1 Heat Loss due to Air Leakage			6.2.6 Sensible Gain due to Air Leakage																																																									
$HL_{airb} = LR_{airh} \times \frac{V_b}{3.6} \times DTD_h \times 1.2$ 0.234 x 509.87 x 41 °C x 1.2 = 5912 W = 20170 Btu/h			$HG_{salb} = LR_{airc} \times \frac{V_b}{3.6} \times DTD_c \times 1.2$ 0.076 x 509.87 x 6 °C x 1.2 = 285 W = 972 Btu/h																																																									
5.2.3.2 Heat Loss due to Mechanical Ventilation			6.2.7 Sensible heat Gain due to Ventilation																																																									
$HL_{vairb} = PVC \times DTD_h \times 1.08 \times (1 - E) \quad \times 2 \text{ HRV / ERV's}$ 300 CFM x 74 °F x 1.08 x 0.25 = 6010 Btu/h			$HL_{vairb} = PVC \times DTD_h \times 1.08 \times (1 - E)$ 300 CFM x 11 °F x 1.08 x 0.25 = 891 Btu/h																																																									
5.2.3.3 Calculation of Air Change Heat Loss for Each Room (Floor Multiplier Section)																																																												
$HL_{airr} = Level \ Factor \times HL_{airbv} \times \{(HL_{agcr} + HL_{bgcr}) \div (HL_{agclevel} + HL_{bgclevel})\}$																																																												
Level	Level Factor (LF)	HLairve Air Leakage + Ventilation Heat Loss (Btu/h)	Level Conductive Heat Loss: (HL _{clevel})	Air Leakage Heat Loss Multiplier (LF x HLairbv / HLlevel)																																																								
1	0.5	20,170	11,056	0.912																																																								
2	0.3		17,070	0.354																																																								
3	0.2		16,044	0.251																																																								
4	0		0	0.000																																																								
5	0		0	0.000																																																								
*HLairbv = Air leakage heat loss + ventilation heat loss *For a balanced or supply only ventilation system HLairve = 0																																																												
				Michael O'Rourke BCIN# 19669 																																																								

HEAT LOSS AND GAIN SUMMARY SHEET

MODEL: 5008	OPT IN-LAW	BUILDER: ROYAL PINE HOMES
SFQT: 4382	LO# 95286	SITE: VALES OF HUMBER SOUTH

DESIGN ASSUMPTIONS

HEATING	°F	COOLING	°F
OUTDOOR DESIGN TEMP.	-2	OUTDOOR DESIGN TEMP.	86
INDOOR DESIGN TEMP.	72	INDOOR DESIGN TEMP. (MAX 75°F)	75
		WINDOW SHGC	0.60

BUILDING DATA

ATTACHMENT:	DETACHED	# OF STORIES (+BASEMENT):	3
FRONT FACES:	EAST	ASSUMED (Y/N):	Y
AIR CHANGES PER HOUR:	2.50	ASSUMED (Y/N):	Y
AIR TIGHTNESS CATEGORY:	TIGHT	ASSUMED (Y/N):	Y
WIND EXPOSURE:	SHELTERED	ASSUMED (Y/N):	Y
HOUSE VOLUME (ft ³):	64821.0	ASSUMED (Y/N):	Y
INTERNAL SHADING:	BLINDS/CURTAINS	ASSUMED OCCUPANTS:	7
INTERIOR LIGHTING LOAD (Btu/h/ft ²):	1.55	DC BRUSHLESS MOTOR (Y/N):	Y
FOUNDATION CONFIGURATION	BCIN_1	DEPTH BELOW GRADE:	7.0 ft
LENGTH: 66.0 ft	WIDTH: 42.0 ft	EXPOSED PERIMETER:	216.0 ft

2012 OBC - COMPLIANCE PACKAGE**Component****Compliance Package
SB-12 PERFORMANCE****Nominal Min. Eff.**

Ceiling with Attic Space Minimum RSI (R)-Value	60	59.22
Ceiling Without Attic Space Minimum RSI (R)-Value	31	27.65
Exposed Floor Minimum RSI (R)-Value	31	29.80
Walls Above Grade Minimum RSI (R)-Value	22+1.5	21.40
Basement Walls Minimum RSI (R)-Value	20	21.12
Below Grade Slab Entire surface > 600 mm below grade Minimum RSI (R)-Value	-	-
Edge of Below Grade Slab ≤ 600 mm Below Grade Minimum RSI (R)-Value	10	10
Heated Slab or Slab ≤ 600 mm below grade Minimum RSI (R)-Value	10	11.13
Windows and Sliding Glass Doors Maximum U-Value	1.6	-
Skylights Maximum U-Value	2.6	-
Space Heating Equipment Minimum AFUE	0.96	-
HRV Minimum Efficiency	75%	-
Domestic Hot Water Heater Minimum EF	0.9	-


INDIVIDUAL BCIN: 19669

MICHAEL O'ROURKE



Residential Foundation Thermal Load Calculator

Supplemental tool for CAN/CSA-F280

Weather Station Description		
Province:	Ontario	
Region:	Brampton	
Site Description		
Soil Conductivity:	Normal conductivity: dry sand, loam, clay	
Water Table:	Normal (7-10 m, 23-33 ft)	
Foundation Dimensions		
Floor Length (m):	20.1	 Insulation Configuration
Floor Width (m):	12.8	
Exposed Perimeter (m):	0.0	
Wall Height (m):	3.0	
Depth Below Grade (m):	2.13	
Window Area (m ²):	2.2	
Door Area (m ²):	1.9	
Radiant Slab		
Heated Fraction of the Slab:	0	
Fluid Temperature (°C):	33	
Design Months		
Heating Month	1	
Foundation Loads		
Heating Load (Watts):		2282

TYPE: 5008
LO# 95286

OPT IN-LAW


Air Infiltration Residential Load Calculator

Supplemental tool for CAN/CSA-F280

Weather Station Description				
Province:	Ontario			
Region:	Brampton			
Weather Station Location:	Open flat terrain, grass			
Anemometer height (m):	10			
Local Shielding				
Building Site:	Suburban, forest			
Walls:	Heavy			
Flue:	Heavy			
Highest Ceiling Height (m):	7.01			
Building Configuration				
Type:	Detached			
Number of Stories:	Two			
Foundation:	Full			
House Volume (m ³):	1835.5			
Air Leakage/Ventilation				
Air Tightness Type:	Energy Star Detached (2.5 ACH)			
Custom BDT Data:	ELA @ 10 Pa.		1713.5 cm ²	
	2.50		ACH @ 50 Pa	
Mechanical Ventilation (L/s):	Total Supply		Total Exhaust	
	70.8		70.8	
Flue Size				
Flue #:	#1	#2	#3	#4
Diameter (mm):	0	0	0	0
Natural Infiltration Rates				
Heating Air Leakage Rate (ACH/H):	0.234			
Cooling Air Leakage Rate (ACH/H):	0.076			


TYPE: 5008
LO# 95286

OPT IN-LAW



HVAC LEGEND								3.		
SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION	2.	UPDATED EQUIPMENT	JUL/2024
	SUPPLY AIR GRILLE		6" SUPPLY AIR BOOT ABOVE		14"x8" RETURN AIR GRILLE		RETURN AIR STACK ABOVE	1.	REVISED TO PERFORMANCE PATH	APR/2022
	SUPPLY AIR GRILLE 6" BOOT		SUPPLY AIR STACK FROM 2nd FLOOR		30"x8" RETURN AIR GRILLE		RETURN AIR STACK 2nd FLOOR	No.	Description	Date
	SUPPLY AIR BOOT ABOVE		6" SUPPLY AIR STACK 2nd FLOOR		FRA- FLOOR RETURN AIR GRILLE		REDUCER	REVISIONS		
ALL DRAWINGS, CALCULATIONS AND SPECIFICATIONS ARE THE PROPERTY OF HVAC DESIGNS LTD.© AND MAY NOT BE REPRODUCED, MODIFIED OR ALTERED WITHOUT EXPRESSED WRITTEN CONSENT. THE DRAWINGS ARE DATED AND USE OF THESE DRAWINGS AFTER ONE YEAR FROM THE DATED NOTED IS NOT AUTHORIZED. CONTRACTOR SHALL CHECK ALL CONDITIONS BEFORE PROCEEDING WITH WORK. LATEST MUNICIPAL APPROVED DRAWINGS ONLY TO BE USED DURING INSTALLATION OF HEATING SYSTEM. HVAC DESIGNS LTD. IS NOT LIABLE FOR ANY CLAIMS ARISING FROM UNAUTHORIZED USE OF THE DRAWINGS OR FROM ANY CHANGES TO ACCEPTED STANDARDS AND/OR THE ONTARIO BUILDING CODE.						I Michael O'Rourke have reviewed and take responsibility for the design work and am qualified under division C.3.2.5 of the building code.		Michael O'Rourke BCIN # 19669 HVAC Designs Ltd.		
Client		Project Name		375 Finley Ave. Suite 202 - Ajax, Ontario L1S 2E2 Tel. 905.619.2300 - 905.420.5300 Fax 905.619.2375 Email: info@hvacdesigns.ca Web: www.hvacdesigns.ca Specializing in Residential Mechanical Design Services		Installation to comply with the latest Ontario Building Code. All supply branch outlets shall be equipped with a manual balancing damper. Ductwork which passes through the garage or unheated spaces shall be adequately insulated and be gas-proofed.		SB-12 PERFORMANCE		
ROYAL PINE HOMES		VALES OF HUMBER SOUTH BRAMPTON, ONTARIO		4382 sqft		OPT IN-LAW 5008		Sheet Title		
								BASEMENT HEATING LAYOUT		
								Date MAR/2022		
								Scale 3/16" = 1'-0"		
								BCIN# 19669		
								LO# 95286		


	S/A	R/A	FANS
2ND	15	6	3
1ST	15	3	3
BAS	7	1	0



GROUND FLOOR PLAN, EL. 'A'

HVAC LEGEND								3.																			
SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION	2.	UPDATED EQUIPMENT	JUL/2024																	
	SUPPLY AIR GRILLE		6" SUPPLY AIR BOOT ABOVE		14"x8" RETURN AIR GRILLE		RETURN AIR STACK ABOVE	1.	REVISED TO PERFORMANCE PATH	APR/2022																	
	SUPPLY AIR GRILLE 6" BOOT		SUPPLY AIR STACK FROM 2nd FLOOR		30"x8" RETURN AIR GRILLE		RETURN AIR STACK 2nd FLOOR	No.	Description	Date																	
	SUPPLY AIR BOOT ABOVE		6" SUPPLY AIR STACK 2nd FLOOR		FRA- FLOOR RETURN AIR GRILLE		REDUCER	REVISIONS																			
ALL DRAWINGS, CALCULATIONS AND SPECIFICATIONS ARE THE PROPERTY OF HVAC DESIGNS LTD.© AND MAY NOT BE REPRODUCED, MODIFIED OR ALTERED WITHOUT EXPRESSED WRITTEN CONSENT. THE DRAWINGS ARE DATED AND USE OF THESE DRAWINGS AFTER ONE YEAR FROM THE DATED NOTED IS NOT AUTHORIZED. CONTRACTOR SHALL CHECK ALL CONDITIONS BEFORE PROCEEDING WITH WORK. LATEST MUNICIPAL APPROVED DRAWINGS ONLY TO BE USED DURING INSTALLATION OF HEATING SYSTEM. HVAC DESIGNS LTD. IS NOT LIABLE FOR ANY CLAIMS ARISING FROM UNAUTHORIZED USE OF THE DRAWINGS OR FROM ANY CHANGES TO ACCEPTED STANDARDS AND/OR THE ONTARIO BUILDING CODE.						I Michael O'Rourke have reviewed and take responsibility for the design work and am qualified under division C.3.2.5 of the building code.		 Michael O'Rourke BCIN # 19669 HVAC Designs Ltd.		SB-12 PERFORMANCE																	
Client		 375 Finley Ave. Suite 202 - Ajax, Ontario L1S 2E2 Tel. 905.619.2300 - 905.420.5300 Fax 905.619.2375 Email: info@hvacdesigns.ca Web: www.hvacdesigns.ca Specializing in Residential Mechanical Design Services Installation to comply with the latest Ontario Building Code. All supply branch outlets shall be equipped with a manual balancing damper. Ductwork which passes through the garage or unheated spaces shall be adequately insulated and be gas-proofed.				<table><tr><td></td><td>S/A</td><td>R/A</td><td>FANS</td></tr><tr><td>2ND</td><td>15</td><td>6</td><td>3</td></tr><tr><td>1ST</td><td>15</td><td>3</td><td>3</td></tr><tr><td>BAS</td><td>7</td><td>1</td><td>0</td></tr></table>					S/A	R/A	FANS	2ND	15	6	3	1ST	15	3	3	BAS	7	1	0	Sheet Title	
	S/A									R/A	FANS																
2ND	15									6	3																
1ST	15									3	3																
BAS	7									1	0																
ROYAL PINE HOMES										FIRST FLOOR HEATING LAYOUT																	
Project Name										Date																	
VALES OF HUMBER SOUTH BRAMPTON, ONTARIO		MAR/2022																									
		Scale																									
		3/16" = 1'-0"																									
		BCIN# 19669																									
OPT IN-LAW 5008		LO#																									
4382 sqft		95286																									

	S/A	R/A	FANS
2ND	15	6	3
1ST	15	3	3
BAS	7	1	0



SECOND FLOOR PLAN, EL. 'A'

HVAC LEGEND								3.		
SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION	2.	UPDATED EQUIPMENT	JUL/2024
	SUPPLY AIR GRILLE		6" SUPPLY AIR BOOT ABOVE		14"x8" RETURN AIR GRILLE		RETURN AIR STACK ABOVE	1.	REVISED TO PERFORMANCE PATH	APR/2022
	SUPPLY AIR GRILLE 6" BOOT		SUPPLY AIR STACK FROM 2nd FLOOR		30"x8" RETURN AIR GRILLE		RETURN AIR STACK 2nd FLOOR	No.	Description	Date
	SUPPLY AIR BOOT ABOVE		6" SUPPLY AIR STACK 2nd FLOOR		FRA- FLOOR RETURN AIR GRILLE		REDUCER	REVISIONS		




ALL DRAWINGS, CALCULATIONS AND SPECIFICATIONS ARE THE PROPERTY OF HVAC DESIGNS LTD.© AND MAY NOT BE REPRODUCED, MODIFIED OR ALTERED WITHOUT EXPRESSED WRITTEN CONSENT. THE DRAWINGS ARE DATED AND USE OF THESE DRAWINGS AFTER ONE YEAR FROM THE DATED NOTED IS NOT AUTHORIZED. CONTRACTOR SHALL CHECK ALL CONDITIONS BEFORE PROCEEDING WITH WORK. LATEST MUNICIPAL APPROVED DRAWINGS ONLY TO BE USED DURING INSTALLATION OF HEATING SYSTEM. HVAC DESIGNS LTD. IS NOT LIABLE FOR ANY CLAIMS ARISING FROM UNAUTHORIZED USE OF THE DRAWINGS OR FROM ANY CHANGES TO ACCEPTED STANDARDS AND/OR THE ONTARIO BUILDING CODE.

I Michael O'Rourke have reviewed and take responsibility for the design work and am qualified under division C.3.2.5 of the building code.


Michael O'Rourke BCIN # 19669
HVAC Designs Ltd.

SB-12 PERFORMANCE

Client	ROYAL PINE HOMES	 375 Finley Ave. Suite 202 - Ajax, Ontario L1S 2E2 Tel. 905.619.2300 - 905.420.5300 Fax 905.619.2375 Email: info@hvacdesigns.ca Web: www.hvacdesigns.ca Specializing in Residential Mechanical Design Services Installation to comply with the latest Ontario Building Code. All supply branch outlets shall be equipped with a manual balancing damper. Ductwork which passes through the garage or unheated spaces shall be adequately insulated and be gas-proofed.	<table><tr><td></td><td>S/A</td><td>R/A</td><td>FANS</td></tr><tr><td>2ND</td><td>15</td><td>6</td><td>3</td></tr><tr><td>1ST</td><td>15</td><td>3</td><td>3</td></tr><tr><td>BAS</td><td>7</td><td>1</td><td>0</td></tr></table>					S/A	R/A	FANS	2ND	15	6	3	1ST	15	3	3	BAS	7	1	0	Sheet Title	SECOND FLOOR HEATING LAYOUT
	S/A		R/A	FANS																				
2ND	15		6	3																				
1ST	15		3	3																				
BAS	7		1	0																				
Project Name	VALES OF HUMBER SOUTH BRAMPTON, ONTARIO					Date	MAR/2022																	
						Scale	3/16" = 1'-0"																	
							BCIN# 19669																	
OPT IN-LAW 5008	4382 sqft					LO#	95286																	



HVAC LEGEND								3.		
SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION	2.	UPDATED EQUIPMENT	JUL/2024
	SUPPLY AIR GRILLE		6" SUPPLY AIR BOOT ABOVE		14"x8" RETURN AIR GRILLE		RETURN AIR STACK ABOVE	1.	REVISED TO PERFORMANCE PATH	APR/2022
	SUPPLY AIR GRILLE 6" BOOT		SUPPLY AIR STACK FROM 2nd FLOOR		30"x8" RETURN AIR GRILLE		RETURN AIR STACK 2nd FLOOR	No.	Description	Date
	SUPPLY AIR BOOT ABOVE		6" SUPPLY AIR STACK 2nd FLOOR		FRA- FLOOR RETURN AIR GRILLE		REDUCER	REVISIONS		

ALL DRAWINGS, CALCULATIONS AND SPECIFICATIONS ARE THE PROPERTY OF HVAC DESIGNS LTD. © AND MAY NOT BE REPRODUCED, MODIFIED OR ALTERED WITHOUT EXPRESSED WRITTEN CONSENT. THE DRAWINGS ARE DATED AND USE OF THESE DRAWINGS AFTER ONE YEAR FROM THE DATED NOTED IS NOT AUTHORIZED. CONTRACTOR SHALL CHECK ALL CONDITIONS BEFORE PROCEEDING WITH WORK. LATEST MUNICIPAL APPROVED DRAWINGS ONLY TO BE USED DURING INSTALLATION OF HEATING SYSTEM. HVAC DESIGNS LTD. IS NOT LIABLE FOR ANY CLAIMS ARISING FROM UNAUTHORIZED USE OF THE DRAWINGS OR FROM ANY CHANGES TO ACCEPTED STANDARDS AND/OR THE ONTARIO BUILDING CODE.

I Michael O'Rourke have reviewed and take responsibility for the design work and am qualified under division C.3.2.5 of the building code.

Michael O'Rourke BCIN # 19669
HVAC Designs Ltd.

SB-12 PERFORMANCE

Client		 375 Finley Ave. Suite 202 - Ajax, Ontario L1S 2E2 Tel. 905.619.2300 - 905.420.5300 Fax 905.619.2375 Email: info@hvacdesigns.ca Web: www.hvacdesigns.ca Specializing in Residential Mechanical Design Services	<table><tr><td></td><td>S/A</td><td>R/A</td><td>FANS</td></tr><tr><td>2ND</td><td>15</td><td>6</td><td>3</td></tr><tr><td>1ST</td><td>15</td><td>3</td><td>3</td></tr><tr><td>BAS</td><td>7</td><td>1</td><td>0</td></tr></table>					S/A	R/A	FANS	2ND	15	6	3	1ST	15	3	3	BAS	7	1	0	Sheet Title	
	S/A						R/A	FANS																
2ND	15						6	3																
1ST	15						3	3																
BAS	7	1	0																					
ROYAL PINE HOMES		ELEVATION C HEATING LAYOUT																						
Project Name		Installation to comply with the latest Ontario Building Code. All supply branch outlets shall be equipped with a manual balancing damper. Ductwork which passes through the garage or unheated spaces shall be adequately insulated and be gas-proofed.		Date																				
VALES OF HUMBER SOUTH BRAMPTON, ONTARIO				MAR/2022																				
OPT IN-LAW 5008				Scale																				
4382 sqft		BCIN# 19669		LO#																				
				95286																				