


Lot 53

Product Dimensions - Double Ovens

Cabinet Dimensions - Double Ovens




27" (68.6 cm) models

- A. 51 1/4" (130.0 cm) max. overall height
- B. 25 1/4" (64.6 cm) max. recessed width
- C. 48 1/4" (124.0 cm) recessed height
- D. 23 1/4" (59.1 cm) max. recessed depth
- E. 27" (68.6 cm) overall width
- F. 12" (30.5 cm) from back of control panel to start of strain relief
- G. 66" (167.6 cm) flexible conduit length

30" (76.2 cm) models

- A. 51 1/4" (130.0 cm) max. overall height
- B. 28 1/4" (72.2 cm) max. recessed width
- C. 48 1/4" (124.0 cm) recessed height
- D. 23 1/4" (59.1 cm) max. recessed depth
- E. 30" (76.2 cm) overall width
- F. 12" (30.5 cm) from back of control panel to start of strain relief
- G. 66" (167.6 cm) flexible conduit length



27" (68.6 cm) models

- A. 27" (68.6 cm) min. cabinet width
- B. 1" (2.5 cm) top of cutout to bottom of upper cabinet door
- C. 14 1/4" (37.5 cm) bottom of cutout to floor is recommended. 4" (10.2-37.5 cm) bottom of cutout to floor is acceptable.
- D. 25 1/2" (64.8 cm) cutout width
- E. 1 1/2" (3.8 cm) min. bottom of cutout to top of cabinet door
- F. 60 1/4" (153.6 cm) recommended cutout height
- G. 24" (60.7 cm) cutout depth

30" (76.2 cm) models

- A. 30" (76.2 cm) min. cabinet width
- B. 1" (2.5 cm) top of cutout to bottom of upper cabinet door
- C. 14 1/4" (37.5 cm) bottom of cutout to floor is recommended. 4" (10.2-37.5 cm) bottom of cutout to floor is acceptable.
- D. 28 1/2" (72.4 cm) min. cutout width
- E. 1 1/2" (3.8 cm) min. bottom of cutout to top of cabinet door
- F. 50 1/4" (127.6 cm) recommended cutout height
- G. 24" (60.7 cm) cutout depth

*NOTE: The cutout height can be between 48 1/4" and 52 1/4" (124.1 cm and 132.6 cm) for double ovens.

Page 1 of 6

RECEIVED

MAY 19 2021

30" (76.2 CM) AND 36" (91.4 CM) GAS BUILT-IN COOKTOP

20753

PRODUCT MODEL NUMBERS

KCGS350E	KCGS950E	MGC9530D	WCG75US0D
KCGS356E	KCGS956E	MGC9536D	WCG97US0D
KCGS550E	MGC7430D	WCG51US0D	WCG97US6D
KCGS556E	MGC7536D	WCG51US6D	

GAS SUPPLY REQUIREMENTS

Type of Gas

Natural Gas

- This cooktop is factory set for use with Natural Gas. If converting to LP gas, see the "LP Gas Conversion" instructions provided in the package containing literature. The model/serial rating plate located on the underside of the cooktop base has information on the types of gas that can be used. If the types of gas listed do not include the type of gas available, check with the local gas supplier.

LP Gas Conversion

Conversion must be done by a qualified service technician.

No attempt shall be made to convert the cooktop from the gas specified on the model/serial rating plate for use with a different gas without consulting the serving gas supplier. See the Gas Conversion instructions provided in the package containing literature.

Gas Supply Line

- Provide a gas supply line of 3/4" (1.9 cm) rigid pipe to the cooktop location. A smaller size pipe on longer runs may result in insufficient gas supply. Pipe-joint compounds that resist the action of LP gas must be used. Do not use TEFLON™ tape. With LP gas, piping or tubing size should be 1/2" minimum. Usually, LP gas suppliers determine the size and materials used in the system.

Flexible metal appliance connector:


- If local codes permit, use a 1/2" or 3/4" I.D. flexible stainless steel tubing gas connector, designed by CSA to connect the cooktop to the rigid gas supply line.



- A 1/2" male pipe thread is needed for connection to the female pipe threads of the inlet to the cooktop pressure regulator.
- Do not kink or damage the flexible metal tubing when moving the cooktop.

• Must include a shutoff valve

The supply line must be equipped with a manual shutoff valve. This valve should be located in the same room but external to the cooktop opening, such as an adjacent cabinet. It must be accessible without removing the cooktop, and it should be in a location that allows ease of opening and closing. Do not block access to shutoff valve. The valve is for turning on or shutting off gas to the cooktop.



- A. Gas supply line
- B. Shutoff valve "open" position
- C. To cooktop

TEFLON is a registered trademark of E. I. Du Pont de Nemours and Company

ELECTRICAL REQUIREMENTS

- A 120 volt, 60 Hz, AC only, 15-amp, fused electrical circuit is required. A time-delay fuse or circuit breaker is also recommended. It is recommended that a separate circuit serving only this cooktop be provided.
- Electronic ignition systems operate within wide voltage limits, but proper grounding and polarity are necessary. Check that the outlet provides 120-volt power and is correctly grounded.

RECEIVED
MAY 19 2021

20753

KCGS556ESS and KCGS950ESS Models



A. 21" (53.3 cm)
B. 30" (76.2 cm)
C. 19 1/2" (49.2 cm)
D. 28 1/2" (72.1 cm)

E. 3 1/2" (8.6 cm)
F. 4 1/2" (11.5 cm)
G. 1 1/2" (3.8 cm)



KCGS556ESS and KCGS956ESS Models




A. 21" (53.3 cm)
B. 36 1/2" (92.0 cm)
C. 19 1/2" (49.2 cm)
D. 34 3/8" (88.1 cm)

E. 3 1/2" (8.6 cm)
F. 4 1/2" (11.5 cm)
G. 1 1/2" (3.8 cm)



All Other 30" (76.2 cm) Models




A. 21" (53.3 cm)
B. 30" (76.2 cm)
C. 18 1/2" (46.0 cm)
D. 28 1/2" (72.1 cm)

E. 3 1/2" (8.6 cm)
F. 4 1/2" (11.5 cm)
G. 1 1/2" (3.8 cm)



All Other 30" (91.4 cm) Models



A. 21" (53.3 cm)
B. 36 1/2" (91.4 cm)
C. 18 1/2" (46.0 cm)
D. 33 1/2" (85.7 cm)

E. 3 1/2" (8.6 cm)
F. 4 1/2" (11.5 cm)
G. 1 1/2" (3.8 cm)



RECEIVED

MAY 19 2021

CABINET DIMENSIONS


20753



Side View



Front View




- A. 13" (33.0 cm) recommended upper cabinet depth.
- B. 30" (76.2 cm) for 30" models; 36" (91.4 cm) for 36" models.
- C. 18" (45.7 cm) minimum clearance from upper cabinet to countertop within minimum horizontal clearances to cooktop.
- D. 30" (76.2 cm) minimum clearance between top of cooktop platform and bottom of uncovered wood or metal cabinet. 24" (61 cm) minimum clearance if bottom of wood or metal cabinet is covered by not less than 1/2" (12.7 mm) flame retardant millboard covered with not less than No. 28 MSG sheet steel, 0.015" (0.04 cm) stainless steel, or 0.024" (0.06 cm) aluminum or 0.020" (0.05 cm) copper.
- E. 36" (91.4 cm) top of countertop to floor.
- F. Gas line opening - Wall: anywhere 5" (12.7 cm) below underside of countertop. Cabinet floor: anywhere within 6" (15.2 cm) of rear wall is recommended.

RECEIVED
MAY 19 2021

70753

Back Wall



Countertop Front Edge

Cutout (Product Opening) Dimensions					
30" (76.2 cm) Models					
Models	A			B	
	Min	Recommended	Max	Min	Max
KCGS550 and KCGS950 All Other 30" (76.2 cm) Models	28 1/2" (72.4 cm)	28 3/4" (73.4 cm)	29 1/4" (74.3 cm)	19 1/2" (49.5 cm)	19 1/4" (50.2 cm)
	28 1/2" (72.4 cm)	28 5/8" (73.4 cm)	29 1/4" (74.3 cm)	19" (48.3 cm)	19 1/2" (49.5 cm)
36" (91.4 cm) Models					
KCGS550 and KCGS950 All Other 36" (91.4 cm) Models	34 1/2" (88.4 cm)	35 1/4" (89.4 cm)	35 9/16" (90.3 cm)	19 1/2" (49.5 cm)	19 1/4" (50.2 cm)
	33 1/2" (86.0 cm)	34 1/4" (87.0 cm)	35 1/2" (89.5 cm)	19" (48.3 cm)	19 1/2" (49.5 cm)
KCGS360, KCGS366, MGC9036, WCG97USQ, WCG97US6	H and I added together must be at least 48" (122.0 cm) with each side individually being at least 8" (20.3 cm)			H and I added together must be at least 48" (122.0 cm) with each side individually being at least 12" (30.5 cm)	
	Both have to be 8" (20.3 cm) or more			Both have to be 8" (20.3 cm) or more	

Side Walls (Combustible Surfaces)	
Models	H and I
KCGS5 and KCGS9	H and I added together must be at least 48" (122.0 cm) with each side individually being at least 8" (20.3 cm)
KCGS360, KCGS366, MGC9036, WCG97USQ, WCG97US6	H and I added together must be at least 48" (122.0 cm) with each side individually being at least 12" (30.5 cm)
All Other Models	Both have to be 8" (20.3 cm) or more

Back Wall and Countertop Front Dimensions			
Models	C	D	E
KCGS550 and KCGS950	25" (63.5 cm)	2" (7.3 cm)	2 1/2" (6.9 cm)
All Other Models			3 1/2" (7.9 cm)

NOTES: After making the countertop cutout, some installations may require notching down the base cabinet side walls to clear the cooktop base. To avoid this modification, use a base cabinet with sidewalls wider than the cutout.

If cabinet has a drawer, a 4" (10.2 cm) depth clearance from the countertop to the top of the drawer (or other obstruction) in base cabinet is required. The drawer depth may need to be shortened to avoid interfering with the regulator.

IMPORTANT: If a built-in wall oven is to be installed below this cooktop, the grounded outlet and gas supply piping must be located in an adjacent cabinet.

This cooktop and its gas and electrical supply sources must be installed before the undercounter built-in wall oven is installed.

RECEIVED

MAY 19 2021

KRMF606E KRMF708E

Electrical: A 115 volt, 60 Hz AC only, 15- or 20-amp fused, grounded electrical supply is required. It is recommended that a separable circuit serving only your refrigerator be provided. Use an outlet that cannot be turned off by a switch. Do not use an extension cord.

Water: A cold water supply with water pressure between 35 and 120 psi (241 and 827 kPa) is required to operate the water dispenser and ice maker. If you have questions about your water pressure, call a licensed, qualified plumber.

NOTE: If the water pressure is less than what is required, the flow of water from the water dispenser could decrease or ice cubes could be hollow or irregular shaped.

Reverse Osmosis Water Supply:

IMPORTANT: The pressure of the water supply coming out of a reverse osmosis system going to the water inlet valve of the refrigerator needs to be between 35 and 120 psi (241 and 827 kPa).

If a reverse osmosis water filtration system is connected to your cold water supply, the water pressure to the reverse osmosis system needs to be a minimum of 40 to 60 psi (276 to 414 kPa).

LOCATION REQUIREMENTS




IMPORTANT: This refrigerator is designed for indoor, household use only.

To ensure proper ventilation for your refrigerator, allow for a 1/2\" (1.25 cm) of space on each side and at the top. Allow for a 1\" (2.54 cm) space behind the refrigerator. If your refrigerator has an ice maker, allow extra space at the back for the water line connections. When installing your refrigerator next to a food wall, leave a 3 1/2\" (9.5 cm) minimum space between the refrigerator and wall to allow the door to swing open.

NOTE: This refrigerator is intended for use in a location where the temperature ranges from a minimum of 55°F (13°C) to a maximum of 110°F (43°C). The preferred room temperature range for optimum performance, which reduces electricity usage and provides superior cooling, is between 60°F (15°C) and 90°F (32°C). It is recommended that you do not install the refrigerator near a heat source, such as an oven or radiator.

Bottom Mount Refrigerator

PRODUCT DIMENSIONS



Model Size	Height - Overall "A"	Height - Top of Cabinet "B"	Depth - With Handles "C"	Depth - Without Handles "D"	Depth - Cabinet Only "E"	Width - Cabinet "F"
25.6	70 1/4" (178.1 cm)	64 1/2" (163.7 cm)	38 1/2" (97.1 cm)	34 1/2" (87.7 cm)	29" (73.7 cm)	36" (91.4 cm)

RECEIVED

MAY 19 2021