



## APPLIANCE SPEC INFORMATION SHEET

STE & LOT: 385

DATE: Nov 11/16

SITING: ☐ Standard ☐ Reverse

### RANGE

- ☐ 30" (STD)  
☐ 36"  
☐ 48"  
☒ GAS *std.*  
☐ COOKTOP (APRON)  
☐ COOKTOP (DROPIN)
- ☐ AMPS \_\_\_\_\_  
☐ AMPS \_\_\_\_\_  
☐ AMPS \_\_\_\_\_

### REFRIGERATOR

- ☐ STANDARD OPENING 36" X 72"  
☐ BUILT IN FRIDGE  
☐ WATERLINE REQUIRED *std*  
☐ PANELLED/INTEGRATED  
☐ FLUSH INSET

### WALL OVENS

- ☐ 30"  
☐ SINGLE  
☐ DOUBLE  
☐ STEAM OVEN  
☐ WARMING DRAWER
- ☐ AMPS \_\_\_\_\_  
☐ AMPS \_\_\_\_\_  
☐ AMPS \_\_\_\_\_  
☐ AMPS \_\_\_\_\_  
☐ AMPS \_\_\_\_\_

### MICROWAVES

- ☐ BUILT IN MICRO  
☐ MICRO TRIM KIT  
☐ OVER THE RANGE
- ☐ AMPS \_\_\_\_\_  
☐ MODEL \_\_\_\_\_  
☐ AMPS \_\_\_\_\_

### HOOD FANS

- ☐ CHIMNEY (CENTRE VENT)  
☐ UNDER CABINET  
☐ FLUSH INSET
- ☐ 6 INCH (STD)  
☒ 8 INCH  
☐ 10 INCH

### DISHWASHER

- ☐ 24" (STD SIZE)

### LAUNDRY

- ☐ FRONT LOADING SIDE BY SIDE  
☐ STACKABLE

\_\_\_\_ Additional charges may apply for cabinetry, electrical and plumbing in order to accommodate the specs given by the homeowner.

\_\_\_\_ **NOTE:** It is the Purchaser's responsibility to coordinate delivery, installation and hook up of appliances and to ensure they are installed as per Manufacturer's specifications after closing.

\_\_\_\_ Purchaser acknowledges responsibility for providing correct specification for such appliances. The purchaser agrees to deliver forthwith to the Builder the manufacturer's appliance specifications where the size exceeds the standard openings.

\_\_\_\_ If specs not received, the standard openings as determined by Zancor Homes will be provided. If rework/repair is required due to late specs received, additional costs will be applied.

Appliance Specs not received, DUE BY: \_\_\_\_\_

Appliance Specs RECEIVED

Purchaser Signature \_\_\_\_\_ Date \_\_\_\_\_

*yes*  
*hood fan to follow*

Purchaser Signature \_\_\_\_\_ Date \_\_\_\_\_

36" CONTEMPORARY GAS COOKTOP - 5 BURNERS



CG365C/S




FEATURES

- 20,000 Btu burner for faster boils
- Lower tier of dual-stacked burner lets you simmer and melt
- Continuous cast-iron grates for easy movement of pots and pans
- Spark ignition system re-ignites when flame goes out
- Dual-stacked, sealed burners for higher highs, lower lows
- Easy-clean seamless burner pan
- Illuminated control knobs
- Stunning minimalist design sits virtually flush to countertop
- Rigorously tested in our U.S. manufacturing facilities for decades of use
- Exceptional 24/7 support from our Customer Care team in Madison

ACCESSORIES

- Center burner wok grate
- Signature red, black or brushed stainless control knobs
- High altitude conversion kit


Accessories available through an authorized Sub-Zero dealer. For local dealer information, visit [subzero-wolf.com/locator](http://subzero-wolf.com/locator)



KNOB OPTIONS



TOP CONFIGURATION



COOKTOP SPECIFICATIONS

- 2 - 9,200 Btu Burner
- 2 - 12,000 Btu Burner
- 1 - 20,000 Btu Burner

385 HES  
COPLES

440


36" CONTEMPORARY GAS COOKTOP - 5 BURNERS



PRODUCT SPECIFICATIONS


Model	CG365C/S
Dimensions	35 15/16"W x 6 3/4"H x 20 15/16"D
Weight	100 lb
Electrical Supply	120 VAC, 60 Hz
Electrical Service	15 amp dedicated circuit
Gas Supply	3/4" rigid pipe
Gas Inlet	1/2" NPT female
Power Cord Length	6 feet
Receptacle	3-prong grounding-type

ELECTRICAL AND GAS




385 Candles

DIMENSIONS



STANDARD INSTALLATION



NOTE: Shaded area above countertop indicates minimum clearance to combustible surfaces. Combustible materials cannot be located within this area. Maximum facade thickness 1\"/>

460

36" INTEGRATED OVER-AND-UNDER REFRIGERATOR/FREEZER WITH ICE MAKER -  
PANEL READY

SUB-ZERO



IT-36CI

FEATURES

- Dual refrigeration keeps food fresher longer
- Air purification system fights spoilage, odors
- Water-filtration system for ice reduces contaminants, chlorine taste and odor
- Automatic ice maker with "max ice" feature
- Over-and-under refrigerator/freezer storage
- Ready to be fitted with custom cabinetry or stainless steel panels
- Rigorously tested in our U.S. manufacturing facilities to ensure at least 20 years of heavy use
- Exceptional 24/7 support from our Customer Care team based in Madison, Wisconsin and just footsteps from our factory

ACCESSORIES

- Dual installation kits
- Stainless steel front panels with tubular or pro handles
- Stainless steel kickplate
- Stainless steel side enclosure
- Stainless steel top enclosure
- Reduced toe kick divider for toe kicks from 3.875" to 2"
- Stainless steel tubular handles
- Stainless steel pro handles
- Replacement water filter

Accessories are available through an authorized Sub-Zero dealer. For local dealer information, visit [subzero-wolf.com/locator](http://subzero-wolf.com/locator)



HANDLE ACCESSORIES

PRO



TUBULAR



PRODUCT DETAILS

REFRIGERATOR

- 3 Adjustable glass shelves
- 1 Stationary shelf
- Crisper drawer with 2 adjustable dividers
- Adjustable dairy compartment
- 2 Adjustable door shelves
- 1 Stationary door shelf

FREEZER

- 3 Adjustable drawer dividers
- Removable ice container
- Automatic ice maker

285403


760

## SUB ZERO


## DIMENSIONS

115 VAC, 60 Hz  
15 amp dedicated circuit  
1/4" OD copper, braided stainless steel or PEX tubing

## PLUMBING




## STANDARD INSTALLATION



This illustration is intended for interior reference only and may not represent the exterior of the model being specified.

Costs \$87



NOTE: 3 1/2" (89) finished returns will be visible and should be finished to match caddybox.





30" E SERIES CONTEMPORARY BUILT-IN SINGLE OVEN



SO30CE/B/TH

FEATURES

- 10 cooking modes make meals easy
- Three adjustable oven racks
- Cobalt blue porcelain interior
- Self clean, delayed start, timed cook, Sabbath mode and more
- Installs flush with surrounding cabinetry
- Dual convection oven for faster, more consistent cooking
- Temperature probe lets you know when it's done
- Rigorously tested in our U.S. manufacturing facilities for decades of use
- Exceptional 24/7 support from our Customer Care team in Madison
- Hidden bake element and recessed broil element

ACCESSORIES

- 30" baking sheet
- Bake stone kit (stone, rack and peel)
- Dehydration kit (racks and door stop)
- Full-extension easy glide oven rack
- Temperature probe and broiler pan
- Set of three standard oven racks

Accessories available through an authorized Sub-Zero dealer.  
For local dealer information, visit [subzero-wolf.com/locator](http://subzero-wolf.com/locator)



385  
CASHES

10


30" E SERIES CONTEMPORARY BUILT-IN SINGLE OVEN




PRODUCT SPECIFICATIONS

Model	SO30CE/B/TH	
Dimensions	29 7/8"W x 27 7/8"H x 23 3/4"D	25"W x 16 1/2"H x 19"D
Oven 1 Interior Dimensions		
Overall Capacity	4.5 cu ft	
Usable Capacity	2.8 cu ft	
Door Clearance	22"	
Weight	273 lb	
Electrical Supply	240/208 VAC, 60 Hz	
Electrical Service	30 amp dedicated circuit	
Conduit Length	4 feet	


ELECTRICAL



DIMENSIONS



STANDARD INSTALLATION



NOTE: Location of electrical supply within opening may require additional cabinet depth.

285 codes

400

30" E SERIES CONTEMPORARY CONVECTION STEAM OVEN



CSO30CM/B/TH WITH BLACK HANDLE


**FEATURES**

- More than 25% larger than similar units
- 10 cooking modes make meals easy
- Easy-access water tank provides 90 minutes of steam cooking
- Installs flush with cabinetry or integrated into your kitchen design
- Gourmet mode adjusts time, temperature, humidity for perfect results
- Rigorously tested in our U.S. manufacturing facilities for decades of use
- Exceptional 24/7 support from our Customer Care team in Madison
- Steam mode captures nutrition, flavor and color
- Reheat mode rehydrates leftovers flavorfully
- Auto Steam Bake mode for bagels, breads, pastries
- Convection mode for consistent results and beautiful browning
- Convection Humid mode seals in moisture for juicy results
- Convection Steam mode for foods tender inside, crisped outside
- Slow Roast mode cooks dinner while you're away
- Recipes mode cooks from collection of built-in recipes
- "Keep Warm" mode
- Program in when you want your dish to be ready
- Temperature probe lets you know when it's done
- Two pans, four rack positions

**ACCESSORIES**

Black Handle

Accessories available through an authorized Sub-Zero dealer.  
For local dealer information, visit [subzero-wolf.com/locator](http://subzero-wolf.com/locator)



385  
CASHES

Feb



30" E SERIES CONTEMPORARY CONVECTION STEAM OVEN



PRODUCT SPECIFICATIONS

Model	CSO30CM/B/TH with Black Handle	
Dimensions	29 7/8"W x 17 7/8"H x 21 1/2"D	
Oven Interior Dimensions	17 7/8"W x 11"H x 15 3/4"D	
Capacity	1.8 cu ft	
Door Clearance	14 3/16"	
Weight	80 lb	
Electrical Supply	240/208 VAC, 60 Hz	
Electrical Service	20 amp dedicated circuit	
Power Cord Length	6 feet	


ELECTRICAL

E


LOCATE ELECTRICAL SUPPLY IN ADJACENT CABINET WITHIN REACH OF POWER CORD

E

DIMENSIONS



STANDARD INSTALLATION



Electrical supply must be located in adjacent cabinet within 3' (9 m) of opening.

385  
car files

80

## 15" SIGNATURE SERIES WINE RESERVE


HP15WS-3 | 15" INDOOR MODEL  
HP15WO-3 | 15" OUTDOOR MODEL



QUALITY & INNOVATION  
THAT **INSPIRES**



Glass Door Model



Solid Door Model

### GENERAL SIGNATURE SERIES FEATURES

- Zero-clearance hinging allows for abutment with surrounding cabinetry
- Best in Class 525 Btu commercial-grade compressor
- Front-vented, RAPIDcool forced-air refrigeration system
- Commercial-grade stainless steel interior and exterior
- **Industry Exclusive** convertible door design allows all doors the ability to be converted to wood overlay from stainless steel
- **Industry Exclusive** adjustable, full-extension pull-out shelves (drawer models and beer dispenser excluded)
- Stainless-steel ball-bearing glides provide smooth movement of shelves
- Adjustable Crisp White and Cool Blue LED lighting
- Low E, UV-coated glass provides industry leading insulation and protection.
- State-of-the-art digital control module
- Optional door locks and Industry-Exclusive drawer locks (factory installed)
- Stacking kit available
- Indoor and outdoor models available
- Also available - 15" Refrigerator, Beverage Center, Beer Dispenser and Clear Ice Maker
- 2.8 cubic feet of capacity
- Industry Best Three Year Warranty plus additional three years on sealed system

### HP15WS-3/WO-3 FEATURES

- Available with solid stainless steel door, solid wood overlay door, stainless steel glass door or wood overlay glass door
- Includes five (5) full-extension pull-out wine shelves
- Wine shelves feature stainless steel fronts
- Product capacity is 20 wine bottles
- Wine Reserve temperature 45° - 65°F

385 Castles

Form No.HP15WS-3  
Rev. 01.15.16


8300 W. Good Hope Rd. • Milwaukee, WI 53223 • (800) 558-5592 • Fax: (414) 353-7069 • [perlick.com](http://perlick.com)  
*Perlick is committed to continuous improvement. Therefore, we reserve the right to change specifications without warning.*

BCO

PRODUCT SPECIFICATIONS	
Overall Width	14-7/8" (37.78 cm)
Overall Height	34-1/4" (86.96 cm)
Overall Depth	24" (60.96 cm)
Opening Width	15" (38.1 cm)
Opening Height	34-3/8" (87.31 cm)
Opening Depth	24" (60.96 cm)
Refrigerated Volume	2.8 cu. ft.
Door Swing Clearance	16" (40.64 cm) minimum
Electrical	115V, 60Hz, 1 Phase, 2.3 amps
Plumbing	None Required
Shipping Weight	175 lbs (79.38 kg)

INDOOR MODELS	
HP15WS-3-1L*	Solid stainless steel door, hinge left
HP15WS-3-2L*	Solid wood overlay door, hinge left
HP15WS-3-3L*	Stainless steel glass door, hinge left
HP15WS-3-4L*	Wood overlay glass door, hinge left
OUTDOOR MODELS	
HP15WO-3-1L*	Solid stainless steel door, hinge left
HP15WO-3-2L*	Solid wood overlay door, hinge left
HP15WO-3-3L*	Stainless steel glass door, hinge left
HP15WO-3-4L*	Wood overlay glass door, hinge left

\* Also available hinge right



388 Castles


Handwritten signature/initials.




## ELECTRIC DRYER

### PRODUCT MODEL NUMBERS

WED7505F, WED7540F, WED7590F, WED75HEF,  
WED7740F, WED77HEF, WED90HEF, WED92HEF, WED85HEF




Front view




Side view

Back view

### Recommended installation clearances



**NOTE:** Most installations require a minimum of 5" (127 mm) clearance behind dryer for exhaust vent with elbow. See "Venting Requirements."



\*0" (0 mm) spacing is allowed for straight-back venting only. For steam models only, inlet hose must not be kinked.

### Spacing for recessed area or closet installation

All dimensions show recommended and minimum spacing allowed.

- Additional spacing should be considered for ease of installation and servicing.
- Additional clearances might be required for wall, door, and floor moldings.
- Additional spacing should be considered on all sides of the dryer to reduce noise transfer.
- For closet installation with a door, minimum ventilation openings in the top and bottom of the door are required. Louvered doors with equivalent ventilation openings are acceptable.
- Companion appliance spacing should also be considered.

38S Ca87es

W10775223A

05/2016

INSTALLATION REQUIREMENTS

ELECTRICAL REQUIREMENTS

To supply the required 3- or 4-wire, single phase, 120/240 volt, 60 Hz, AC only electrical supply (or 3- or 4-wire, 120/208 volt electrical supply, if specified on the serial/rating plate) on a separate 30-amp circuit, fused on both sides of the line. Connect to an individual branch circuit. Do not have a fuse in the neutral or grounding circuit.

WATER (STEAM MODELS ONLY) REQUIREMENTS


The dryer must be connected to the cold water faucet using new inlet hoses (not supplied). Do not use old hoses. Do not overtighten. Damage to the coupling can result.

VENTING REQUIREMENTS


Exhaust venting: Exhaust your dryer to the outside. 4" (102 mm) diameter vent is required. Rigid or flexible metal exhaust vent must be used. Do not use plastic or metal foil vet. Exhaust hood must be at least 12" (305 mm) from the ground or any object that may be in the path of the exhaust.

Exhaust hoods:


Recommended styles:



Louvered Hood



Box Hood



Angled Hood

Acceptable style:

- Determine vent path:**
- Select route that will provide straightest and most direct path outdoors.
  - Plan installation to use fewest number of elbows and turns.
  - When using elbows or making turns, allow as much room as possible.
  - Bend vent gradually to avoid kinking.
  - Use as few 90° turns as possible.

Determine vent length and elbows needed for best drying performance:

- Use the following "Vent System Charts" to determine type of vent material and hood combinations acceptable to use.
- NOTE:** Do not use vent runs longer than those specified in "Vent System Charts."
- Shorten life of dryer.
  - Reduce performance, resulting in longer drying times and increased energy usage.

The "Vent System Charts" provide venting requirements that will help achieve best drying performance.

Standard Vent System Chart		
Number of 90° elbows	Type of vent	Angled hoods
0	Rigid metal	64 ft. (20 m)
1	Rigid metal	54 ft. (16.5 m)
2	Rigid metal	44 ft. (13.4 m)
3	Rigid metal	35 ft. (10.7 m)
4	Rigid metal	27 ft. (8.2 m)

Long Vent System Chart		
Number of 90° elbows	Type of vent	Angled hoods
0	Rigid metal	160 ft. (48.8 m)
1	Rigid metal	150 ft. (45.7 m)
2	Rigid metal	140 ft. (42.7 m)
3	Rigid metal	130 ft. (39.6 m)
4	Rigid metal	120 ft. (36.6 m)

To determine if your model has a long vent system, refer to the type code located on the serial number plate in the inner door well. Example: An electric model would be **DALV** (Long Vent) – ELE – XXXXXX-XXX.

**NOTE:** For long vent systems, use of box/louvered hoods will improve venting, regardless of length.

385 Castles

# D5636XXLSHI

Turbo Drying  
Top tray for bowls and cutlery  
Upper basket type: Premium  
Lower basket type: Premium  
Separate removable basket  
Number of place settings: 16

**Top tray functions**  
InstantLift™ - smart height adjustment of the top tray  
Divisible and removable trays  
Rack for knives and utensils  
Rack for bowls and cups  
Telescopic rails

**Upper basket functions**  
Tight mesh base  
Multi position wire shelf left  
Multi position wire shelf right  
Fixed pin rows  
Fixed glass support  
Wide knife stand  
Guide rails with ball bearings

**Lower basket functions**  
Tight mesh base  
Foldable/divisible pin rows rear  
Separate removable basket

**Programs**  
Sanitation wash  
Normal wash  
Heavy wash  
Quick wash  
Hygiene wash  
Delicate wash  
ECO wash  
Upper half  
Lower half

**Options**  
Delayed start  
**Cleaning systems**  
Number of spray zones: 9  
Number of spray arms: 3  
WideClean™ - extra washing power for pots and pans  
SCS - Super Cleaning System™  
Aqua Level™ Sensor  
Stainless steel spray arms

**Drying system**  
Turbo Drying™  
**Features**  
8 stainless steel parts  
Time remaining indicator  
Voice signal for the end of washing cycle  
Hidden heater  
Kidsafe - lockable controls

**Water safety**  
Few sealing points outside the container  
Long lasting seam welded tank  
Waterproof external base  
Exterior float  
Aqua Detect™ Sensor  
Aqua Level™ Sensor  
Stand-by water protection  
Yes  
Max time water intake  
Sound alarm  
Anti-block drain pump

**Installation**  
Adjustable feet  
Multi fit outlet hose  
Fixed high loop outlet hose  
Trim kit


EAN code: 3839942043871  
code: 492612

**General**  
Product: Dishwasher  
Mode of installation: Built-in  
Size: XXL  
LED display  
Number of programs: 9  
Noise level: 46 dB(A)  
Number of baskets: 3  
EAN code: 3839942043871

**Dimensions and installation**  
Height: 34 1/4 (870 mm)  
Width: 23 15/16 (603 mm)  
Depth: 22 7/8 (581 mm)  
Packaging height: 36 5/8 (930 mm)  
Packaging width: 25 3/16 (640 mm)  
Packaging depth: 26 3/4 (680 mm)  
Length electrical cord: 46 7/16 (1180 mm)  
Length inlet hose: 66 1/8 (1680 mm)  
Length outlet hose: 41 3/4 (1060 mm)  
Weight net: 101 lbs  
Weight gross: 109 lbs

**Technical information**  
Voltage: 120 V  
Current: 15 A

**Consumption**  
Energy consumption/cycle: 0,87 kWh



383 Castles

40



## 24" SIGNATURE SERIES REFRIGERATOR

**HP24RS-3** | 24" INDOOR MODEL  
**HP24RO-3** | 24" OUTDOOR MODEL

**Perlick®**

QUALITY & INNOVATION  
THAT **INSPIRES**



Solid Door Model



Glass Door Model



Drawer Model



### GENERAL SIGNATURE SERIES FEATURES

- Zero-clearance hinging allows for abutment with surrounding cabinetry
- Perlick's exclusive commercial-grade, 1,000 Btu variable-speed compressor
- Front-vented, RAPIDcool forced-air refrigeration system
- Commercial-grade stainless steel interior and exterior
- **Industry Exclusive** convertible door design allows all doors the ability to be converted to wood overlay from stainless steel
- **Industry Exclusive** adjustable, full-extension pull-out shelves (drawer models excluded)
- Stainless-steel ball-bearing glides provide smooth movement of shelves
- Low E, UV-coated glass provides industry leading insulation and protection.
- Adjustable Crisp White and Cool Blue LED lighting
- State-of-the-art digital control module
- Optional door locks and Industry-Exclusive drawer locks (factory installed)
- Stacking kit available
- Indoor and outdoor models available
- Also available - 24" Freezer, Beverage Center, Wine Reserve, Beer Dispenser, and Dual-Zone Wine Reserve
- 5.2 cubic feet of capacity
- Industry Best Three Year Warranty plus additional three years on sealed system

### HP24RS-3/RO-3 FEATURES

- Available with solid stainless steel door, solid wood overlay door, stainless steel glass door, wood overlay glass door, stainless steel drawers or wood overlay drawers
- Door models include two (2) full-extension pull-out shelves
- Refrigerator rated for both food and beverage storage
- Refrigerator temperature 33° - 42°F

385 Castles

Form No HP24R-3

Rev. 06.15.2015





## Front-Loading Washer


### PRODUCT MODEL NUMBERS

WFW7590F, WFW75HEF, WFW90HEF,  
WFW92HEF

### PRODUCT MODEL NUMBERS


WFW7590F, WFW9290F, WFW85HEF

#### Washer Dimensions:




Recessed or closet installation -  
stacked washer and dryer


#### Washer Dimensions:



Recessed area or closet installation (washer only):




\* Add spacing of 1" (25 mm) on all sides of washer/dryer.



\* Add spacing of 1" (25 mm) on all sides of washer.


38 S Castles

Custom cabinet installation (washer only):



\*\* Recommended 4" (102 mm), minimum 1.5" (38 mm)

Undercounter installation - washer only:



All dimensions show recommended spacing allowed, except for closet door ventilation openings which are the minimum required.

For each arrangement, consider allowing more space for ease of installation and servicing, and spacing for companion appliances and clearances for walls, doors, and floor moldings.

Space must be large enough to allow door to fully open. Add spacing of 1" (25 mm) on all sides of washer to reduce noise transfer. If a closet door or louvered door is installed, top and bottom air openings in door are required.

ELECTRICAL REQUIREMENTS


A 120 volt, 60 Hz., AC only, 15- or 20-amp, fused electrical supply is required. A time-delay fuse or circuit breaker is recommended. It is recommended that a separate circuit serving only this appliance be provided.

DRAIN SYSTEM

Drain system can be installed using a floor drain, wall standpipe, floor standpipe, or laundry tub. Select method you need.


**IMPORTANT:** To avoid siphoning, only 4.5" (114 mm) of drain hose should be inside standpipe. Always secure drain hose with cable tie.

Floor standpipe drain system




Minimum diameter for a standpipe drain: 2" (51 mm). Minimum carry-away capacity: 17 gal. (64 L) per minute. A 1/4" (6 mm) diameter to 1" (25 mm) diameter Standpipe Adapter Kit is available (Part Number 3363920). Top of standpipe must be at least 30" (762 mm) high; install no higher than 96" (2,44 m) from bottom of washer. If you have an overhead sewer and need to pump higher than 96" (2,44 m), a sump pump and associated hardware are needed. See "Alternate Parts".

Wall standpipe drain system




See requirements for floor standpipe drain system.

Laundry tub drain system



Minimum capacity: 20 gal. (76 L). Top of laundry tub must be at least 30" (762 mm) above floor; install no higher than 96" (2,44 m) from bottom of washer.

Floor drain system



Floor drain system requires a Siphon Break Kit (Part Number 285834), 2 Connector Kits (Part Number 285835), and an Extension Drain Hose (Part Number 285863) that may be purchased separately. See "Alternate Parts". Minimum siphon break height: 28" (710 mm) from bottom of washer. (Additional hoses may be needed.)