



**COAST Wholesale
APPLIANCES**

3/15/17

#1 - 1748 CREDITSTONE ROAD, VAUGHAN, ONT.
L4K 5V8 *** TOLL FREE 1-888-745-0622
PH:(905)303-6909 FX:(905)856-5325
TORONTO LINE:(416)745-0622



"Innovative Products for Builders, Designers & Home Owners"

Sold To: IAN RAMPADARAT
LOT 20 PINE RIVER
ANGUS
ON L9L 9L9

Ship To: IAN RAMPADARAT
LOT 20 PINE RIVER
206 BROWNLEY LANE
ANGUS
ON L0M 1B6

SALES ORDER

APR 20 2017

Customer Class			Builders Allowance Name /# / Amount \$			Ship Via	Invoice #
003 BLDR CUST SALES				#	\$	COAST	1413592
Sales Representatives			Address:	Terms	Prov.Tax #	Customer #	Order #
F8 WAYNE W 18,7			LOT 20 PINE RIVER	CASH SALES		HT177	1869544-01
			Shipping Location	Date Ordered	Date Allocated	Date Required	Order Type
			WOODBIDGE WHSE	15MAR17	25SEP17		REGULAR ORDER
			Customer P.O.#	Job #:	Change Order #:		
Quantity Ordered	Quantity BackOrd	Quantity Shipped	Model / Description			Price	Extension
1	1		KRFC302ESS	KITCHEN AID 22CUFT FRENCH DOOR B/M SS			
				36", COUNTER DEPTH REFRIGERATOR			
1	1		KCGS956ESS	KITCHENAID 36" 5 BURNER GAS COOKTOP			
				WITH GRIDDLE			
1	1		KOCE500ESS	KITCHEN AID 30" COMBO,MICRO/WALLOVEN SS			
1	1		KDTE204ESS	KITCHEN AID DISHWASHER FULLY INTEGRATED			
				6 CYCLES SS			
1	1		KITCHENAID REBATE	KITCHENAID REBATE			
1	1		EPR628SS	ELICA PALERMO 28" WIDE 600 CFM 3 SPEED			
				HOOD			
1	1		EXXHDL36	ELICA HOOD LINER 36"			
1	1		INSTALLATION HOOKUP	INSTALLATION - HOOKUP WATERLINE TO FRIDG			
1	1		INSTALLATION- C/TOP	INSTALLATION COOK TOP			
1	1		INSTALLATION-W/OVEN	INSTALLATION WALL OVEN			
1	1		INSTALLATION/H/FAN	INSTALLATION OF HOOD FAN			
1	1		INSTALLATION/DISH	INSTALLATION OF DISHWASHER			
1	1		LEVEL FRIDGE	LEVEL FRIDGE			
				INSTALL WINE FRIDGE			
			Legend: * = Eco Fee Applicable, K = Keep for future shipment				
			CHEQUE 1,200.00			PAYMENT	
						SUBTOTAL	
						PST	
						DEL/FUEL S/C	
						HST	
						TOTAL	

Report to:					
SM	CR	Shipper	Date Shipped	EXTENDED WARRANTY	
				ACCEPTED	REJECTED

GST# 81398 6668


PAGE 1 OF 3

Customer Copy

1869544-01/0000001

NOW 15 LOCATIONS TO SERVE YOU

www.coastappliances.com



**COAST Wholesale
APPLIANCES**

#1 - 1748 CREDITSTONE ROAD, VAUGHAN, ONT.
L4K 5V8 *** TOLL FREE 1-888-745-0622
PH:(905)303-6909 FX:(905)856-5325
TORONTO LINE:(416)745-0622



"Innovative Products for Builders, Designers & Home Owners"

Sold To: IAN RAMPADARAT
LOT 20 PINE RIVER
ANGUS
ON L9L 9L9

Ship To: IAN RAMPADARAT
LOT 20 PINE RIVER
206 BROWNLEY LANE
ANGUS
ON L0M 1B6

SALES ORDER

Customer Class			Builders Allowance Name /# / Amount \$			Ship Via	Invoice #
003 BLDR CUST SALES				#	\$	COAST	1413592
Sales Representatives			Address:	Terms	Prov.Tax #	Customer #	Order #
F8 WAYNE W 18,7			LOT 20 PINE RIVER	CASH SALES		HT177	1869544-01
			Shipping Location	Date Ordered	Date Allocated	Date Required	Order Type
			WOODBIDGE WHSE	15MAR17	25SEP17		REGULAR ORDER
			Customer P.O.#	Job #:	Change Order #:		
Quantity Ordered	Quantity BackOrd	Quantity Shipped	Model / Description			Price	Extension
1	1		PFA PACKAGE FREIGHT ALLOWANCE INCLUDED				
1	1		BA FRIDGE BASE CONTRACT BUILDERS ALLOW FRIDGE BASE				
1	1		BA RANGE BASE CONTRACT BUILDERS ALLOW RANGE BASE				
1	1		BA D/W BASE CONTRACT BUILDERS ALLOW D/W BASE				
1	1		BA WASHER BASE CONTRACT BUILDERS ALLOW WASHER BASE				
1	1		BA DRYER BASE CONTRACT BUILDERS ALLOW DRYER BASE				
1	1		BA HOSES BA HOSES				
1	1		BA BUILDERS ALLOWANCE				
1	1		CREDIT FOR INSTALL STANDARD PACKAGE				
1	1		8462 4 YS EXTENDED SINGLE APPLIANCE				
			(3000.00 - 4999.99))				
1	1		8463 KITCHENAID FRIDGE KRFC302ESS				
			4 YS EXTENDED SINGLE APPLIANCE				
			(5000.00 - 7499.99))				
1	1		8460 KITCHEN WALL OVEN KOCE500ESS				
			4 YS EXTENDED SINGLE APPLIANCE				
			(1000.00 - 1499.99))				
1	1		8461 KITCHENAID DISHWASHER KDTE204ESS				
			4 YS EXTENDED SINGLE APPLIANCE				
			Legend: * = Eco Fee Applicable, K = Keep for future shipment			PAYMENT	
			CHEQUE 1,200.00				
						SUBTOTAL	
						PST	
						DEL/FUEL S/C	
						HST	
						TOTAL	

Report to:						
SM	CR	Shipper		Date Shipped	EXTENDED WARRANTY	
					ACCEPTED	REJECTED

GST# 81398 6668

PAGE 2 OF 3

Customer Copy

1869544-01/0000001

NOW 15 LOCATIONS TO SERVE YOU

www.coastappliances.com



**COAST Wholesale
APPLIANCES**

#1 - 1748 CREDITSTONE ROAD, VAUGHAN, ONT.
L4K 5V8 *** TOLL FREE 1-888-745-0622
PH: (905) 303-6909 FX: (905) 856-5325
TORONTO LINE: (416) 745-0622



"Innovative Products for Builders, Designers & Home Owners"

Sold To: IAN RAMPADARAT
LOT 20 PINE RIVER
ANGUS
ON L9L 9L9

Ship To: IAN RAMPADARAT
LOT 20 PINE RIVER
206 BROWNLEY LANE
ANGUS
ON L0M 1B6

SALES ORDER

Customer Class			Builders Allowance Name /# / Amount \$			Ship Via	Invoice #
003 BLDR CUST SALES				#	\$	COAST	1413592
Sales Representatives			Address:	Terms	Prov.Tax #	Customer #	Order #
F8 WAYNE W 18,7			LOT 20 PINE RIVER	CASH SALES		HT177	1869544-01
			Shipping Location	Date Ordered	Date Allocated	Date Required	Order Type
			WOODBIDGE WHSE	15MAR17	25SEP17		REGULAR ORDER
			Customer P.O.#	Job #:		Change Order #:	
Quantity Ordered	Quantity BackOrd	Quantity Shipped	Model / Description			Price	Extension
1	1		8461 (1500.00 - 2999.99)) KITCHENAID GAS COOKTOP KCG956ESS 4 YS EXTENDED SINGLE APPLIANCE				
1	1		KUWR204ESB (1500.00 - 2999.99)) KITCHENAID UC WINE FRIDGE KUWR304ESS KITCHEN AID SS WINE COOLER UNDER COUNTER 46 BOTTLE CAPICITY,BLK CABINET RH				
			Legend: * = Eco Fee Applicable, K = Keep for future shipment				
27	27		CHEQUE 1,200.00			PAYMENT	
						SUBTOTAL	
						PST	
						DEL/FUEL S/C	
						HST	
						TOTAL	

Report to:							
SM	CR	Shipper		Date Shipped	EXTENDED WARRANTY		
					ACCEPTED		REJECTED

GST# 81398 6668

PAGE 3 OF 3

Customer Copy

1869544-01/0000001

NOW 15 LOCATIONS TO SERVE YOU

www.coastappliances.com

3/15/17 Lot 20

KitchenAid®

Angus Soul

27" (68.6 cm) and 30" (76.2 cm) Electric Built-In Microwave/Oven Combination

PRODUCT MODEL NUMBERS

KEMS309E

KOCE500E

KOCE507E

ELECTRICAL CONNECTION

If codes permit and a separate ground wire is used, it is recommended that a qualified electrical installer determine that the ground path and the wire gauge are in accordance with local codes.


Check with a qualified electrical installer if you are not sure the oven is properly grounded.

This oven must be connected to a grounded metal, permanent wiring system.

Be sure that the electrical connection and wire size are adequate and in conformance with the National Electrical Code, ANSI/NFPA 70-latest edition or CSA Standards C22.1-94, Canadian Electrical Code, Part 1 and C22.2 No. O-M91-latest edition, and all local codes and ordinances.

To properly install your oven, you must determine the type of electrical connection you will be using and follow the instructions provided for it here.

- Oven must be connected to the proper electrical voltage and frequency as specified on the model/serial/rating plate. See the following illustration.



A. Model/serial/rating plate

- Models rated from 7.3 to 9.6 kW at 240 volts (5.4 to 7.4 kW at 208 volts) require a separate 40-amp circuit. Models rated at 4.8 kW and below at 240 volts (3.6 kW and below at 208 volts) require a separate 30-amp circuit.
- A circuit breaker is recommended.
- Connect directly to the fused disconnect (or circuit breaker box) through flexible, armored or nonmetallic sheathed, copper cable (with grounding wire). See "Make Electrical Connection" section.
- Flexible conduit from the oven should be connected directly to the junction box.
- Do not cut the conduit. The length of conduit provided is for serviceability of the oven.
- A UL listed or CSA approved conduit connector must be provided.
- If the house has aluminum wiring, follow the procedure below:
 - Connect a section of solid copper wire to the pigtail leads.
 - Connect the aluminum wiring to the added section of copper wire using special connectors and/or tools designed and UL listed for joining copper to aluminum.


Follow the electrical connector manufacturer's recommended procedure. Aluminum/copper connection must conform with local codes and industry accepted wiring practices.

For power requirements, refer to the following table.


Model	Voltage	Amperage (L1)*	Amperage (L2)*	Rating (W)
KOCE507E/KOCE500E	120/240	32	30	8000
KOCE507E/KOCE500E	120/208	30	28	6600

*Amperage values noted above are for information purposes only; the units are rated in watts.

PRODUCT DIMENSIONS



Cabinet Dimensions



* NOTE: The cabinet height can be between 41" (104.1 cm) and 41¹/₂" (105.6 cm) for microwave/oven combination.



PALERMO
INSERT

ASPIRE SERIES



Palermo provides professional grade performance, while its 28 $\frac{1}{4}$ " width and 10 $\frac{3}{4}$ " depth enables it to be discreetly installed within standard 12" deep cabinetry, making it ideal for smaller kitchens or where the range hood needs to be out of sight. Palermo has a powerful 600 CFM blower to support most cooking needs. Stylish stainless steel push button controls operate a 3-speed blower and halogen lighting.


Easy maintenance, higher efficiency and a cleaner kitchen are ensured by Elica's patented Baffle Slot Filters, which capture a higher percentage of grease and hold larger volumes of grease than traditional baffle filters. Palermo is designed for standard ducted or recirculating installation.

MODELS

EPR628SS Palermo 28" Stainless

DIMENSIONS

(28 $\frac{1}{4}$ "W x 10 $\frac{3}{4}$ "D x 9 $\frac{1}{2}$ "H)



Halogen Lamps



Stainless Steel
Push Button Controls



Stainless Steel
Baffle Slot Filters

60120 3/15/17

3/15/17

L0620


PALERMO

INSERT
ELICA DESIGN CENTER


Size (in) & Type Finish	28" Wide Insert Stainless Steel
Controls	Stainless Steel Push Button
Illumination	2, 40 Watt Halogen Lamps, 1 Light Intensity (bulbs included)
Installation Type	Ducted or Recirculating Installation Recirculating Kit Sold Separately
Blower Type	600 CFM, 3-Speed Internal
Blower Performance	Speed 1, 190 CFM, 2.1 Sones Speed 2, 350 CFM, 4.7 Sones Speed 3, 600 CFM, 8.1 Sones
Filter Type	2, Dishwasher-Safe, Stainless Steel Baffle Slot
Duct Transition	6" Round with Back Draft Damper (top)
Electrical	120V-60Hz 260 Watts at 4.6 Amps
Warranty	2 Year Parts & Labor, In-Home Service

ACCESSORIES

LINE DRAWING



Optional Recirculating Kit with 2 Carbon Filters

CODE: KIT02770
MODEL: KIT02770Optional 30" Hood Liner
29"W x 17 1/2" - 20 1/2"DCODE: KIT02773
MODEL: EXXHDL30Optional 36" Hood Liner
25"W x 17 1/2" - 20 1/2"DCODE: KIT02774
MODEL: EXXHDL36

CONSUMABLE PARTS

Replacement Grease Filter (1)
CODE: GRI0018064Replacement Carbon Filter (1)
CODE: FB016AReplacement Light Bulb (1)
CODE: 2006EA

Consumable parts are sold in units of one (1). Order accordingly.

3/15/17

60/20

30" (76.2 CM) AND 36" (91.4 CM) GAS BUILT-IN COOKTOP

PRODUCT MODEL NUMBERS

KCGS350E	KCGS950E	MGC9530D	WCG75US0D
KCGS356E	KCGS956E	MGC9536D	WCG97US0D
KCGS550E	MGC7430D	WCG51US0D	WCG97US6D
KCGS556E	MGC7536D	WCG51US6D	

GAS SUPPLY REQUIREMENTS

Type of Gas

Natural Gas:

- This cooktop is factory set for use with Natural gas. If converting to LP gas, see the "LP Gas Conversion" instructions provided in the package containing literature. The model/serial rating plate located on the underside of the cooktop base has information on the types of gas that can be used. If the types of gas listed do not include the type of gas available, check with the local gas supplier.

LP Gas Conversion:

Conversion must be done by a qualified service technician.

No attempt shall be made to convert the cooktop from the gas specified on the model/serial rating plate for use with a different gas without consulting the serving gas supplier. See the Gas Conversion instructions provided in the package containing literature.

Gas Supply Line

- Provide a gas supply line of 3/4" (1.9 cm) rigid pipe to the cooktop location. A smaller size pipe on longer runs may result in insufficient gas supply. Pipe-joint compounds that resist the action of LP gas must be used. Do not use TEFLON[®] tape. With LP gas, piping or tubing size should be 1/2" minimum. Usually, LP gas suppliers determine the size and materials used in the system.

Flexible metal appliance connector:


- If local codes permit, use a 1/2" or 3/4" I.D. flexible stainless steel tubing gas connector, designed by CSA to connect the cooktop to the rigid gas supply line.



- A 1/2" male pipe thread is needed for connection to the female pipe threads of the inlet to the cooktop pressure regulator.
- Do not kink or damage the flexible metal tubing when moving the cooktop.

- Must include a shutoff valve:

The supply line must be equipped with a manual shutoff valve. This valve should be located in the same room but external to the cooktop opening, such as an adjacent cabinet. It must be accessible without removing the cooktop, and it should be in a location that allows ease of opening and closing. Do not block access to shutoff valve. The valve is for turning on or shutting off gas to the cooktop.



A. Gas supply line
B. Shutoff valve "open" position
C. To cooktop

*TEFLON is a registered trademark of E.I. Du Pont De Nemours and Company.


ELECTRICAL REQUIREMENTS

- A 120 volt, 60 Hz, AC only, 15-amp, fused electrical circuit is required. A time-delay fuse or circuit breaker is also recommended. It is recommended that a separate circuit serving only this cooktop be provided.
- Electronic ignition systems operate within wide voltage limits, but proper grounding and polarity are necessary. Check that the outlet provides 120-volt power and is correctly grounded.

PRODUCT DIMENSIONS


3/15/17 16120

KCGS550ESS and KCGS950ESS Models




- | | |
|----------------------|---------------------|
| A. 21" (53.3 cm) | E. 3 3/8" (9.2 cm) |
| B. 30" (76.2 cm) | F. 4 7/8" (11.6 cm) |
| C. 19 3/8" (49.2 cm) | G. 1 3/8" (3.4 cm) |
| D. 28 3/8" (72.1 cm) | |

KCGS556ESS and KCGS956ESS Models




- | | |
|----------------------|---------------------|
| A. 21" (53.3 cm) | E. 3 3/8" (9.2 cm) |
| B. 36 1/4" (92.0 cm) | F. 4 7/8" (11.6 cm) |
| C. 19 3/8" (49.2 cm) | G. 1 7/8" (3.6 cm) |
| D. 34 3/8" (88.1 cm) | |

All Other 30" (76.2 cm) Models



- | | |
|----------------------|---------------------|
| A. 21" (53.3 cm) | E. 3 3/8" (8.6 cm) |
| B. 30" (76.2 cm) | F. 4 1/8" (10.5 cm) |
| C. 18 7/8" (48.0 cm) | G. 1 1/2" (3.8 cm) |
| D. 28 3/8" (72.1 cm) | |


All Other 36" (91.4 cm) Models



- | | |
|----------------------|---------------------|
| A. 21" (53.3 cm) | E. 3 3/8" (8.6 cm) |
| B. 36" (91.4 cm) | F. 4 1/8" (10.5 cm) |
| C. 18 7/8" (48.0 cm) | G. 1 1/2" (3.8 cm) |
| D. 33 3/4" (85.7 cm) | |

CABINET DIMENSIONS


3/15/17 L6/20



- A. 13" (33.0 cm) recommended upper cabinet depth.
- B. 30" (76.2 cm) for 30" models; 36" (91.4 cm) for 36" models.
- C. 18" (45.7 cm) minimum clearance from upper cabinet to countertop within minimum horizontal clearances to cooktop.
- D. 30" (76.2 cm) minimum clearance between top of cooktop platform and bottom of uncovered wood or metal cabinet. 24" [61 cm] minimum clearance if bottom of wood or metal cabinet is covered by not less than 1/4" [0.6 cm] flame retardant millboard covered with not less than No. 28 MSG sheet steel, 0.015" [0.04 cm] stainless steel, or 0.024" [0.06 cm] aluminum or 0.020" [0.05 cm] copper
- E. 36" (91.4 cm) top of countertop to floor.
- F. Gas line opening - Wall: anywhere 5" (12.7 cm) below underside of countertop. Cabinet floor: anywhere within 6" (15.2 cm) of rear wall is recommended.

3/15/17 60620

Back Wall



Cutout (Product Opening) Dimensions						
30" (76.2 cm) Models						
Models	A			B		
	Min	Recommended	Max	Min	Recommended	Max
KCGS550 and KCGS950	28 1/8" (72.4 cm)	28 7/8" (73.4 cm)	29 5/8" (74.3 cm)	19 1/2" (49.5 cm)	19 13/16" (50.2 cm)	20" (50.8 cm)
All Other 30" (76.2 cm) Models	28 1/2" (72.4 cm)	28 7/8" (73.4 cm)	29 5/8" (74.3 cm)	19" (48.3 cm)	19 1/2" (49.5 cm)	20" (50.8 cm)
36" (91.4 cm) Models						
KCGS556 and KCGS956	34 7/8" (88.4 cm)	35 3/16" (89.4 cm)	35 5/8" (90.3 cm)	19 1/2" (49.5 cm)	19 13/16" (50.2 cm)	20" (50.8 cm)
All Other 36" (91.4 cm) Models	33 7/8" (86.0 cm)	34 3/16" (87.0 cm)	35 1/4" (89.5 cm)	19" (48.3 cm)	19 1/2" (49.5 cm)	20" (50.8 cm)

Side Walls (Combustible Surfaces)	
Models	H and I
KCGS5 and KCGS9	H and I added together must be at least 48" (122.0 cm), with each side individually being at least 8" (20.3 cm).
KCGS350, KCGS356, MGC9536, WCG97US0, WCG97US6	H and I added together must be at least 48" (122.0 cm), with each side individually being at least 12" (30.5 cm).
All Other Models	Both have to be 8" (20.3 cm) or more.

Back Wall and Countertop Front Dimensions			
Models	C	D	E
KCGS550 and KCGS950	25" (63.5 cm)	2 7/8" (7.3 cm)	2 3/4" (6.9 cm)
All Other Models			3 1/8" (7.9 cm)

NOTES: After making the countertop cutout, some installations may require notching down the base cabinet side walls to clear the cooktop base. To avoid this modification, use a base cabinet with sidewalls wider than the cutout.

If cabinet has a drawer, a 4" (10.2 cm) depth clearance from the countertop to the top of the drawer (or other obstruction) in base cabinet is required. The drawer depth may need to be shortened to avoid interfering with the regulator.

IMPORTANT: If a built-in wall oven is to be installed below this cooktop, the grounded outlet and gas supply piping must be located in an adjacent cabinet.

This cooktop and its gas and electrical supply sources must be installed before the undercounter built-in wall oven is installed.

3/15/17 L6/20


PRODUCT MODEL NUMBERS

KUBL204E KUBL304E
KUBR204E KUBR304E

Electrical: A 115 volt, 60 Hz., AC only, 15- or 20-amp fused, grounded electrical supply is required. It is recommended that a separate circuit serving only your beverage center be provided. Use an outlet that cannot be turned off by a switch. Do not use an extension cord.

NOTE: Before performing any type of installation, cleaning, or removing a light bulb, unplug beverage center or disconnect power.

OPENING DIMENSIONS




A. 14 3/4" (37.5 cm) utility opening
B. 24" (60.96 cm) minimum opening width

- Height dimensions are shown with the leveling legs extended to the minimum height.
NOTE: When leveling legs are fully extended, add 5/8" (15 mm) to the height dimensions.
- If the floor of the opening is not level with the kitchen floor, shim the opening to make it level with the kitchen floor.

Model	Door Swing
KUBL204E KUBL304E	Left
KUBR204E KUBR304E	Right

LOCATION REQUIREMENTS



To ensure proper ventilation for your beverage center, allow for a 1/4" (6.35 mm) space on each side and at the top. When installing your beverage center next to a fixed wall, leave 2 1/2" (6.35 cm) minimum clearance on the hinge side to allow for the door to swing open.

NOTE: It is recommended that you do not install the beverage center near an oven, radiator, or other heat source. Do not install in a location where the temperature will fall below 55°F (13°C). For best performance, do not install the beverage center behind a cabinet door or block the base grille.

KitchenAid®

FOR THE WAY IT'S MADE®

Undercounter Dishwasher

3/15/17 L0620

PRODUCT MODEL NUMBERS

KDFE204E, KDTE104E, KDTE204E, KDTE254E, KDTM354E, KDTM384E, KDTM404E, KDTM504E, KDTM704E, KDTM804E

Electrical Requirements: 120-volt, 60 Hz, AC-only, 15- or 20-amp. fused electrical supply. Copper wire only. A time delay fuse or circuit breaker and separate circuit is recommended.

If direct wiring dishwasher: Use flexible, armored or nonmetallic, sheathed copper wire with grounding wire that meets the wiring requirements for your home and local codes and ordinances.

Use a UL Listed or CSA Approved conduit connector.

If connecting dishwasher with a power supply cord:

Use power supply cord kit (Part Number 4317824) marked for use with dishwashers. Follow the kit

instructions for installing the power supply cord.

Power supply cord must plug into a grounded three-prong outlet located in the cabinet next to the dishwasher opening. Outlet must meet all local codes and ordinances.

Water Supply Requirements: A hot water line with 20 to 120 psi (138 to 862 kPa) water pressure. Water temperature must be 120°F (49°C) water at dishwasher. Use 3/8" O.D. copper tubing with compression fitting or flexible braided water supply line

Note: 1/2" minimum plastic tubing is not recommended.


Use a 90° elbow with 3/4" hose connection with rubber washer (part number W10273460). Do not solder within 6" (15.2 cm) from water inlet valve.

Drain Requirements: A new drain hose is supplied with your dishwasher. If this is not long enough, use a new drain hose with a maximum length of 12' (3.7 m) (Part No. 3385556) that meets all current AHAM/IAPMO test standards, is resistant to heat and detergent, and fits the 1" (2.5 cm) drain connector of the dishwasher.

Make sure to connect the drain hose to waste tee or disposer inlet above drain trap in house plumbing and 20" (50.8 cm) minimum above the floor. It is recommended

that the drain hose either be looped up and securely fastened to the underside of the counter, or be connected to an air gap.

Make sure to use an air gap if the drain hose is connected to house plumbing lower than 20" (50.8 cm) above subfloor or




floor.

Use 1/2" (1.3 cm) minimum I.D. drain line fittings.

If required, the air gap should be installed in accordance with the air gap installation instructions. When connecting the air gap a rubber hose (not provided) will be needed to connect to the waste tee or disposer inlet.

PRODUCT DIMENSIONS



A. Insulation may be compressed (not used on all models).

B. For panel-ready models, dishwasher depth is 24" (60 cm) not including the 3/4" (1.9 cm) custom door panel.


C. Door handles may protrude forward of the face of the dishwasher; varies by model.

CABINET CUTOUT DIMENSIONS

NOTE: Shaded areas of cabinet walls show where utility connections may be installed.

*Measure from the lowest point on the underside of the countertop. May be reduced to 33½" (85.1 cm) by removing the rear leveling legs from dishwasher.

**Minimum, measured from narrowest point of opening.



16120
3/15/17

ENGLISH CUSTOM HOOD LINER INSTALLATION SHEET

PRELIMINARY INSTRUCTIONS

WARNING

When building a custom hood for an insert or power pack, always follow all applicable construction codes and standards. See the table and illustration below to locate your liner and use corresponding custom hood base dimensions. For the liner installation, only the bottom of the custom hood is needed. Do not finalize the entire custom hood yet, because an access is needed for the insert or power pack electrical connection.

NOTE: We recommend the base of the custom hood should be 3/4" inch thick plywood. We recommend the sides, front and backboard (if included) of the custom hood to be 3/4" thick, assuming standard cabinet widths. The INSIDE DEPTH shown in the table above assumes a minimum cabinet backboard thickness of 3/8".

Consider the shape and size of the power pack to determine the configuration of the custom hood. For more details, refer to the installation manual of the power pack.

For custom hood liner detailed installation instructions, see the reverse of this page.

FRANÇAIS INSTALLATION DU REVÊTEMENT D'ARMOIRE

INSTRUCTIONS PRÉLIMINAIRES

AVERTISSEMENT

Toujours suivre tous les codes en vigueur et standards de la construction lors de la construction d'une armoire de module de hotte encastrable.

Avant de déterminer à quelles dimensions la base de l'armoire correspond le revêtement, voir le tableau et l'illustration ci-dessous. Il n'y a que la base de l'armoire qui est nécessaire pour l'installation du revêtement. Ne pas finaliser l'armoire tout de suite; garder un accès pour le futur branchement électrique du module de hotte encastrable.

NOTE: Nous recommandons que la base de l'armoire soit faite en contreplaqué de 3/4" d'épaisseur. Nous recommandons que l'épaisseur de l'arrière (le cas échéant), de l'avant et des côtés de l'armoire soit de 3/4". La PROFONDEUR INTÉRIEURE indiquée dans le tableau ci-dessus sous-entend que l'épaisseur minimale de l'arrière de l'armoire est de 3/8".

Considérer la forme et la dimension du module de hotte encastrable avant de déterminer la configuration de son armoire. Voir le guide d'installation du module de hotte encastrable pour plus de détails.

Voir le verso de cette page pour les instructions détaillées de l'installation du revêtement d'armoire.

ESPAÑOL INSTALACIÓN DEL LINER PARA CAMPANA

INSTRUCCIONES PRELIMINARES

ADVERTENCIA


Siempre que instale una cubierta para campanas empotrables, debe seguir los códigos y normas de la construcción.


Consulte la tabla y la ilustración que se muestra a continuación para que localice la campana de su elección y utilice la base de dimensiones apropiadas a la campana. Para instalar la cubierta solo necesitará la parte inferior de la campana. No termine la instalación todavía, ya que necesitará dejar una entrada para la conexión eléctrica.

NOTA: Recomendamos que la base de la cubierta sea de triplay de 3/4" de grosor. Recomendamos que los lados, frente y respaldo (en caso de incluirse) de la cubierta sean de 3/4" de grosor, asumiendo estándares de gabinetes. La PROFUNDIDAD INTERIOR mostrada en la tabla asume un respaldo con un grosor mínimo de 3/8". Considere la forma y tamaño de la campana empotrable para determinar la configuración de la cubierta. Para más detalles, haga referencia al manual de instalación de la campana.

Para detalles sobre la instalación del liner, vea el reverso de esta página.

Liner Models Modèles du Revêtement Modelos de liners	Power Pack models Modèles de module de hotte Modelos de campanas empotrables	Inside width - A Largeur int. - A Ancho int. - A	Inside Depth - B Profondeur Intérieure - B Profundidad Interior - B	
			Whithout Backboard Sans panneau arrière Sin parte trasera	Whith Backboard Avec panneau arrière Con parte trasera
EXXHDL30	EAS428SS EPR628SS	29" (73.75cm)	18 1/4" (46.4cm) to 21 1/8" (53.9cm)	17 1/2" (44.5cm) to 20 1/4" (52cm)
EXXHDL36	EAS428SS EPR628SS	35" (89cm)	18 3/8" (46.8cm) to 21 1/4" (54.3cm)	17 13/16" (44.9cm) to 20 1/8" (52.4cm)





ENGLISH CAUTION: Before installing, remove the protective plastic film from all parts.

NOTE: The custom hood liner must be installed before the insert or power pack unit.

CAUTION: FOR ELECTRIC RANGES INSTALLATION: MOUNT THE HOOD SO THAT THE BOTTOM EDGE OF THE HOOD LINER IS NOT LESS THAN 24" (60.9 CM) ABOVE THE COOKING SURFACE (height measured from the cooktop to the lowest part of the Liner).

FOR GAS RANGES INSTALLATION: MOUNT THE HOOD SO THAT THE BOTTOM EDGE OF THE HOOD LINER IS NOT LESS THAN 30" (76.2 CM) ABOVE THE COOKING SURFACE (height measured from the cooktop to the lowest part of the Liner).

- Using the screws provided, temporarily install the main liner plate A to the external base of the cabinet B. Fig. 1.
- **NOTE:** Main liner plate should be positioned in custom hood as far rearward as possible.
- Using a pencil, mark the outline of the future hole for the power pack. Fig. 2.
- Remove the main liner plate from the custom hood.
- Cut the hole in the bottom of the cabinet. Fig. 3.
- Reinstall the main liner plate to the base of the cabinet and secure it with 4 screws. Fig. 4.
- Slide the front panel section C forward into the nose of the cabinet base. Take care not to scratch main liner plate when installing front panel section of liner. Assemble it to the frontal side of the cabinet, using one screw per screw hole. Fig. 5.
- Install the two power pack's mounting brackets D. First, to the bottom face of the cabinet (a).
- **NOTE:** Guided by the pilot holes in the liner kit. Then, with the help of two or more persons, get the power pack hood into the cabinet through the hole and then secure it to the mounting bracket with the provided screws (b). Fig. 6.

FRANÇAIS ATTENTION: Retirer le plastique protecteur de toutes les pièces avant l'installation.

NOTE: Ce revêtement d'armoire doit être installé avant le module de hotte encastrable.

ATTENTION: POUR L'INSTALLATION AVEC CUISINIÈRES ÉLECTRIQUES: MONTER LA HOTTE DE FAÇON À CE QUE LE FOND NE SOIT PAS À MOINS DE 24" (60.9 CM) AU-DESSUS DE LA SURFACE DE LA CUISINIÈRE (hauteur mesurée de la cuisinière à la partie la plus basse de la hotte). **POUR L'INSTALLATION AVEC CUISINIÈRES À GAZ:** MONTER LA HOTTE DE FAÇON À CE QUE LE FOND NE SOIT PAS À MOINS DE 30" (76.2 CM) AU-DESSUS DE LA SURFACE DE LA CUISINIÈRE (hauteur mesurée de la cuisinière à la partie la plus basse de la hotte).

- À l'aide des vis fournies, installer temporairement la plus grande plaque de revêtement A sur la base externe de l'armoire B. Fig. 1.
- **NOTE:** La plus grande plaque de revêtement doit être installée le plus loin possible vers l'arrière de la base externe de l'armoire.
- À l'aide d'un crayon, tracer le contour du trou à découper pour l'insertion du module de hotte encastrable. Fig. 2.
- Retirer la plaque de revêtement de l'armoire.
- Découper le trou dans la base de l'armoire. Fig. 3.
- Installer la plus grande plaque de revêtement à la base externe de l'armoire et la fixer avec 4 vis. Fig. 4.
- Glisser la dernière pièce du revêtement C à l'avant de la base externe de l'armoire. Prendre soin de ne pas égratigner la plus grande plaque de revêtement lors de l'assemblage.
- L'assembler à l'avant de l'armoire en utilisant une vis pour chaque trou de vis. Fig. 5.
- Installez les supports d'installation de la hotte de la cuisinière D. Première, à la face inférieure de l'armoire (a). **NOTE:** guidés par les trous dans le kit, puis, avec l'aide de deux personnes ou plus, déplacer la hotte dans l'armoire à travers le trou et la fixer sur le support d'installation avec les vis fournies (b). Fig. 6.

ESPAÑOL PRECAUCIÓN: Antes de instalar, retire el plástico protector de todas las partes.

NOTA: La cubierta de la campana debe instalarse antes de la campana empotrable.

CUIDADO: PARA LA INSTALACIÓN SOBRE ESTUFAS ELÉCTRICAS: MONTE LA CAMPANA DE MANERA QUE EL BORDE INFERIOR DEL LINER NO ESTE A MENOS DE 24" (60.9 cm) SOBRE LA SUPERFICIE DE COCCIÓN (Altura medida de la superficie de cocción hasta la parte más baja del liner).

PARA LA INSTALACIÓN SOBRE ESTUFAS DE GAS: MONTE LA CAMPANA DE MANERA QUE EL BORDE INFERIOR DEL LINER NO ESTE A MENOS DE 30" (76.2 cm) SOBRE LA SUPERFICIE DE COCCIÓN (Altura medida desde la superficie de cocción hasta la parte más baja del liner).

- Utilice los tornillos que se incluyen, instale provisionalmente la placa principal de la cubierta A a la base externa del gabinete B. Fig. 1.
- **NOTA:** La placa principal de la cubierta debe ser instalada lo más lejos posible hacia atrás de la base externa del gabinete.
- Marque con un bolígrafo el contorno del orificio para la campana empotrable. Fig. 2.
- Retire la placa principal de la cubierta del gabinete.
- Haga el orificio en la parte inferior del gabinete. Fig. 3.
- Vuelva a instalar la placa principal de la cubierta a la base del gabinete y asegúrela con 4 tornillos.
- Deslice la sección frontal del panel C dentro de la nariz de la base de la campana. Asegurarse de no rayar la placa principal de la cubierta. Ensámblela a la parte frontal del gabinete, sujetándola con un tornillo en cada orificio. Fig. 5.
- Instale las dos estafas sujetadoras de la campana D. Primero a la base inferior del gabinete (a).
- **NOTA:** Guíese por los orificios en el liner. Posteriormente, con la ayuda de 2 o más personas, introduzca la campana empotrable en el gabinete a través del orificio y sujete a la estufa con los tornillos provistos (b). Fig. 6.

20620
3/15/17

60620
3/15/17

PRODUCT MODEL NUMBERS

KRFC704F KRFC604F

Electrical: A 115-volt, 60 Hz, AC-only 15- or 20-amp fused, grounded electrical supply is required. It is recommended that a separate circuit serving only your refrigerator and approved accessories be provided. Use an outlet that cannot be turned off by a switch. Do not use an extension cord.

Water: A cold water supply with water pressure between 35 and 120 psi (241 and 827 kPa) is required to operate the water dispenser and ice maker. If you have questions about your water pressure, call a licensed, qualified plumber.



NOTE: If the water pressure is less than what is required, the flow of water from the water dispenser could decrease or ice cubes could be hollow or irregular shaped.

Reverse Osmosis Water Supply:

IMPORTANT: The pressure of the water supply coming out of a reverse osmosis system going to the water inlet valve of the refrigerator needs to be between 35 and 120 psi (241 and 827 kPa).


If a reverse osmosis water filtration system is connected to your cold water supply, the water pressure to the reverse osmosis system needs to be a minimum of 40 to 60 psi (276 to 414 kPa).

PRODUCT DIMENSIONS



Model Size	Height - Overall "A"	Height - Top of Cabinet "B"	Depth - Door Open 90° "C"	Depth - Drawer Open "D"	Depth - With Handles "E"	Depth - Without Handles "F"	Depth - Cabinet Only "G"	Width - Cabinet "H"	Width - Door Open 90° "I"
23.8 cu. ft.	71 ⁷ / ₈ " (182.6 cm)	70 ⁷ / ₈ " (180.0 cm)	43 ³ / ₈ " (111.1 cm)	45 ⁷ / ₈ " (116.5 cm)	31 ¹ / ₂ " (80.0 cm)	28 ¹ / ₈ " (73.3 cm)	24 ³ / ₈ " (61.9 cm)	35 ⁵ / ₈ " (90.5 cm)	43 ³ / ₈ " (110.8 cm)

LOCATION REQUIREMENTS



IMPORTANT: This refrigerator is designed for indoor, household use only.

To ensure proper ventilation for your refrigerator, allow for a 1/2" (1.25 cm) of space on each side and at the top. Allow for a 1" (2.54 cm) space behind the refrigerator. If your refrigerator has an ice maker, allow extra space at the back for the water line connections. When installing your refrigerator next to a fixed wall, leave a 3 3/4" (9.5 cm) minimum space between the refrigerator and wall to allow the door to swing open.

NOTE: This refrigerator is intended for use in a location where the temperature ranges from a minimum of 55°F (13°C) to a maximum of 110°F (43°C). The preferred room temperature range for optimum performance, which reduces electricity usage and provides superior cooling, is between 60°F (15°C) and 90°F (32°C). It is recommended that you do not install the refrigerator near a heat source, such as an oven or radiator.